

290-308 Aldington Road & 59-62 & 63 Abbotts Road (Lots 11-13, DP 253503) Kemps Creek Civil Infrastructure Report

ESR Development (Australia) Pty Ltd MAY 2021 20-748

Commercial in Confidence

All intellectual property rights, including copyright, in designs developed and documents created by AT&L remain the property of this company. Any use made of such design or document without the prior written approval of AT&L will constitute an infringement of the rights of the company which reserves all legal rights and remedies in respect of any such infringement.

The information, including any intellectual property, contained in this proposal is confidential and proprietary to the Company. It may only be used by the person to whom it is provided for the stated purpose for which it is provided and must not be imparted to any third person without the prior written approval of the Company. The Company reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

This report has been prepared in accordance with the terms and conditions of appointment. AT&L cannot accept any responsibility for any use of or reliance on the contents of this report by any third party.

This report may be based upon information supplied by other consultants, contractors and Authorities. To the extent that the report incorporates such material, AT&L takes no responsibility for any loss or damage caused by any error or omission arising from reliance on it.

Document Title	290-308 Aldington Road & 59-62 & 63 Abbotts Road (Lots 11-13, DP 253503) Kemps Creek
Document File Name	R002-03-20-748-SSDA Civil Infrastructure Report.docx
Section	Civil
Document Author	Samip Shah

Issue	Description	Date	Author	Checked	Approved
001	Draft	21/12/20	Samip Shah	\boxtimes	
002	Final	22/12/20	Patrick King	\square	\square
003	TOA REISSUE	09/02/21	Patrick King		
004	Issue for SSDA	14/05/21	Tim Michel		

Document Registration



Contents

1.	Exec	utive Summary1		
2.	. Compliance with Planning SEARs 2			
3.	Ager	cy Consultation		
4.	Intro	duction7		
	4.1.	Background7		
	4.2.	Development Site		
	4.3.	Scope and Staging9		
5.	Eartl	11 nworks		
	5.1.	Existing Geology11		
	5.2.	Proposed Earthworks11		
6.	Sedi	nentation and Erosion Control13		
	6.1.	Sedimentation and Erosion Control (Construction)13		
	6.1.1.	Sources of Pollution13		
	6.1.2.	Potential Impacts		
	6.2.	RUSLE Analysis		
	6.3.	Soil and Water Management Plan15		
	6.3.1.	Overall Strategy15		
	6.3.2.	Design of Sediment and Erosion Control Measures16		
	6.4.	Site Inspection and Maintenance17		
	6.4.1.	Sediment Basin Maintenance		
	6.5.	Conclusion		
7.	Reta	ining Walls19		
8.	Road	Design		
	8.1.	Horizontal and Vertical Geometry		
	8.2.	Internal Road Network		
	8.3.	Pavement		
	8.4.	Batter Design		
	8.5.	Conclusion		
9.	Stori	nwater Management		
	9.1.	Existing Site Stormwater Drainage		



	9.2.	Proposed Site Stormwater Drainage	26
	9.2.1.	External Upstream Stormwater Drainage	28
	9.3.	Stormwater Management Design Criteria Requirements	29
	9.4.	Stormwater Management Strategy Objectives	29
	9.5.	Stormwater Management Strategy Overview	30
	9.6.	Stormwater Management System Modelling	31
	9.6.1.	Hydrological and Hydraulic Modelling	31
	9.6.2.	Hydrological and Hydraulic Design Parameters	32
	9.6.3.	Water Quality Modelling	33
	9.6.4.	Catchments	34
	9.7.	Proposed Stormwater Management Measures	35
	9.7.1.	Rainwater Tanks	35
	9.7.2.	Gross Pollutant Traps	36
	9.7.3.	Bio-Retention Systems	36
	9.7.4.	On-Site Stormwater Detention (OSD)	37
	9.7.5.	Estate-wide Ponds	37
	9.7.6.	Evaporative misting on roof areas	38
	9.8.	Scenario Modelling	39
	9.9.	Model Results	41
	9.9.1.	MUSIC Model Results	41
	9.9.2.	DRAINS Model Results	41
	9.10.	Conclusion	42
1(D. Wate	er Balance	43
	10.1.	General	43
	10.2.	Water Balance Objective	43
	10.3.	Water Balance End Uses	43
	10.4.	Total Site Demands and Non-Potable Reuse Rates	43
	10.5.	Rainwater Reuse	44
	10.6.	Proposed Rainwater Tank Parameters	44
1:	1. Servi	ces Investigation	45
	11.1.	Potable Water	.45



11.1.1.	Existing Potable Water	45
11.1.2.	Proposed Potable Water	45
11.2.	Sewer	46
11.2.1.	Existing Sewer	46
11.2.2.	Proposed Sewer	46
11.3.	Electrical	47
11.3.1.	Existing Electrical	47
11.3.2.	Proposed Electrical	18
11.4.	Telecommunications	18
11.5.	Gas	49
11.6.	Conclusion	49
12. Infra	structure Delivery and Staging	50
12.1.	Staging	50
12.2.	Funding Arrangements	50
APPENDIX	(A – Civil Engineering Plans	51
APPENDIX	(B – DRAINS Model	52
APPENDIX	C – MUSIC Results	54



1. Executive Summary

This report is a summary of the civil infrastructure requirements to aid in the development of the ESR Kemps Creek Logistics Park. The site is located to the east of Aldington Road, and is legally described as Lots 11-13 in DP 253503 and has an area of approximately 32 hectares (ha). It is located within the Penrith City Council Local Government Area (LGA).

The site is located at the eastern end of the Abbotts Road cul-de-sac and has approximately 170m of direct frontage to Abbotts Road and 190m of direct frontage to Aldington Road. The subject site will be developed with proposed lots on either side of the Abbotts Road extension which will provide vehicular access to the proposed lots. Until the connection of Aldington Road to the future Southern Link Road (located to the north) is constructed, the access to the site will be provided from the South bound lane of Mamre Road via Abbotts Road.

The site is located approximately 4km north-west of the future Western Sydney Nancy-Bird Walton Airport, 13km south-east of the Penrith CBD and 40km west of the Sydney CBD.

The site is part of the Broader Western Sydney Employment Area and is zoned land under the *State Environmental Planning Policy (Western Sydney Employment Area) 2009 (SEPP WSEA).*

Consistent with the above, this report has been prepared to support a State Significant Development Application (SSDA) under Part 4 of the *Environmental Planning and Assessment Act 1979* (EP&A Act) to enable the construction of industrial warehouse and distribution buildings.



2. Compliance with Planning SEARs

This report responds to the NSW Planning Secretary's Environmental Assessment Requirements (SEARs) issued by the NSW Department of Planning, Industry and Environment (DPIE) in September 2020 and subsequently updated in December 2020. **Table 1** below summaries all key civil infrastructure issues raised in the SEARs and how they have been addressed in this report.

Key Issue listed in the SEARs	Response
Traffic and Transport	
Connection of development to adjoining sites Detailing how the proposed development connects to adjoining sites to facilitate their future development for their intended purposes	Overall General Arrangement Plan 20-748–C1005 prepared by AT&L indicates Abbotts Road layout which provide connection to adjoining lots to the south east for future development via further extension of Abbotts Road beyond the cul-de-sac currently proposed towards the south-east of the proposed development. It is proposed that detailed coordination of precinct connectivity may occur post formal SSD exhibition stage to enable concurrent development of the <i>Aldington Road Precinct Structure Plan – Local Road</i> <i>Network Structure Plan</i> by TfNSW and Penrith City Council.
Site access and internal road layout Detailed plans of the site access and proposed layout of the internal road and pedestrian network and parking on site in accordance with the relevant Australian Standards and Council's DCP	Access for the site is off Abbotts Road via a proposed three-way junction at the intersection of Abbotts Road and Aldington Road. This three-way junction is designed to provide a future roundabout intersection for future road Aldington Road extension in the southerly direction. The existing Abbotts Road cul-de- sac is proposed to be extended further to the south- easterly direction with a proposed cul-de-sac providing vehicular access to the overall development. Both junctions can provide future connection to the adjoining lands located to the south of the proposed development. Until the connection of Aldington Road to the future Southern Link Road (located to the north) is constructed, the access to Aldington Road will be provided from the North and South bound traffic via a signalised intersection on the South bound lane of the Mamre Road via Abbotts Road.

Table 1: Secretary's Environmental Assessment Requirements addressed in this report

	Refer Roadworks and Stormwater Drainage Plans 20- 748–C1041 to C1047 prepared by AT&L indicating site access along with the proposed road layouts. Note also pedestrian footpath included within the plans. Refer to Architectural plans prepared by NETTLETON TRIBE for internal parking layouts. Abbotts Road and pedestrian networks are proposed to be provided in accordance with Penrith City Council's standard DCP requirements with exception of a proposed wider verge on the shared pathway side to enable a consistent landscape zone within both road verges.
Swept path diagrams Swept path diagrams depicting vehicles entering, exiting and manoeuvring throughout the site	Refer to Vehicle Turn Path drawings 20-748-C1311 to 20-748-C1312 prepared by AT&L for Abbotts Road vehicle analysis. For internal lot turning manoeuvres, refer to the traffic engineering report prepared by ASON.
Road upgrade detail Details of road upgrades, infrastructure works, or new roads or access points required for the development	All upgrade works to Abbotts Road and Aldington Road along with details for new roads within the development have been documented within the AT&L Civil drawings.
Soils and Water	
Topographic assessment A topographic assessment and justification the proposed earthworks are site responsive and contextually appropriate	A Topographic assessment and justification on proposed earthworks are discussed within Section 5 and 7 of this report
Detailed site water balance A detailed site water balance including identification of water requirements for the life of the project, measures that would be implemented to ensure an adequate and secure water supply is available for the development and a detailed description of the measures to minimise the water use at the site	A Water Balance section has been included in this report. Refer Section 10 for all site water balance details, water supply source, usage calculations and efficiency measures.
Satisfactory arrangements for drinking, wastewater and recycled water Demonstration satisfactory arrangements for drinking water, wastewater and if required recycled water	Refer to Section 11 of this report for discussion on water and sewerage for the site along with servicing advice received from Sydney Water

Discharge water quality Characterisation of water quality at the point of discharge to surface and/or groundwater against the relevant water quality criteria (including proposed mitigation measures to manage any impacts to receiving waters and monitoring activities and methodologies) Site specific integrated water management strategy A site-specific integrated water management strategy with details of stormwater/wastewater management system including how it will be designed, operated and maintained, including the capacity of onsite detention system(s), onsite sewage management and measures to treat, reuse (including indicative quantities) or dispose of water	Refer Section 9 of this report where stormwater quality is discussed. Note all stormwater discharge off site will be treated to ensure Penrith City Council's DCP treatment rates are achieved. Refer Appendix C for water treatment train. Refer to Section 9 and 10 of this report for Integrated Water Management strategy.
Measures to minimise water use Description of the measures to minimise water use	Refer to Section 10 of this report for discussion on water re-use across the site using rainwater harvest tanks
Erosion and sediment control Description of the proposed erosion and sediment controls during construction	Sediment and Erosion control measures across the site are discussed in Section 6 of this report. Note all control measures have been designed in accordance with Managing Urban Stormwater – Soils and Construction (Landcom, 2004). Also note the Erosion and Sediment Control plan has been provided for the development assuming that the works will be completed in one stage. As the staging plan is developed, erosion and sediment
Infrastructure Requirements	control measures will be developed to suit the works.
Description of infrastructure required on site A detailed written and/or graphical description of infrastructure required on the site, including any upgrades required	Infrastructure requirements for the site have been documented in the Services and Utilities Coordination Plans prepared by AT&L. Section 11 of this report also discusses all service utilities within and adjacent to the site. Continued coordination with utility infrastructure providers will be undertaken concurrent to formal ESR Developments SSD exhibition to ensure that adequate arrangements are made to ensure required
Identification of infrastructure upgrades	infrastructure will be made available when required. Refer to Section 11 which highlights proposed infrastructure upgrade works required to service the

Identification of any infrastructure upgrades required off-site to facilitate the development, and describe any arrangements to ensure that the upgrades will be implemented in a timely manner and maintained	proposed development. Note all these works will need to be confirmed with the relevant service Authority during detailed design stages. Consultation with each of these Authorities has commenced as part of this SSD process and will continue so during detailed design
Infrastructure delivery and staging plan An infrastructure delivery and staging plan, including a description of how infrastructure on and off-site will be co-ordinated and funded to ensure it is in place prior to the commencement of construction	Refer to Section 12 for indicative infrastructure delivery and staging arrangements.
Development impact on existing utility infrastructure An assessment of the impacts of the development on existing utility infrastructure and service provider assets surrounding the site.	 Any impacts to existing utility infrastructure will be discussed with the relevant service Authority during the detailed design phase. ESR Developments and AT&L has, and will continue to, coordinate with utility authorities regarding the proposed SSD development to identify augmentations required to existing infrastructure because of the proposed development. No significant impacts on existing utility infrastructure surrounding the site are envisaged as part of the proposed ESR Developments SSD development.
Agency Comments	
Penrith City Council	
Water Quality Management and Stormwater Management	
Water quality and water quantity are to be addressed. Post developed flows shall match pre-developed flows. Water quality shall be in accordance with Council's DCP and WSUD policies. It is Council's preference that on-lot water quality and water quantity treatment be provided for rather than large open basins. If large basins are proposed, then they shall remain under the ownership and maintenance of the development site. Council will not accept the dedication of any drainage basin as a public asset.	Refer Section 9 of this report where stormwater quantity and quality are discussed. Note all stormwater discharge off site will be treated to ensure Penrith City Council's treatment rates are achieved. OSD/Water treatment basins and GPTs are proposed to ensure Council's stormwater management requirements are meet. These basins are proposed to remain in the ownership and maintained by the Developer and not be dedicated to Council.



3. Agency Consultation

This report summarises all consultation and correspondence undertaken with the relevant authorities during the design phase. The following table summarises and the relevant correspondence. It should be noted that not all authorities were consulted during the initial design phase.

Table 2: Summary of agency consultation

Agency Consulted	Correspondence
Sydney Water	Sydney Water's input to SEARs for SSD-9138102 dated 4 September 2020 have been acknowledged and servicing arrangements for the site and the Aldington Road Precinct.
Endeavour Energy	During the design phase of the SSDA, AT&L has begun the discussions with Endeavour Energy. As per the email conversation dated 25 th September and the project specifics and EE's comments have been taken into consideration as part of design documentation. Section 11 highlights the EE servicing strategy for the site.
Transport for NSW	TfNSW's input for SSD-10479 dated 16 July 2020 and meeting held on 21 st September 2020 have been acknowledged and these comments have been considered as part design documentation and responded to accordingly.
WaterNSW	WaterNSW input for SSD-913802 dated 25 September 2020 has been acknowledged and these comments have been considered as part design documentation and responded to accordingly



4. Introduction

4.1. Background

This report is a summary of the Masterplan servicing strategy and infrastructure requirements to aid in the development of the ESR Australia's Site located on 290-308 Aldington Road and 59-63 Abbotts Road Kemps Creek.

The Site is located within the Penrith City Council LGA, approximately 4km south of Erskine Park and approximately 9km north-east from the proposed Western Sydney Airport. The Site is legally known as Lots 11-13 DP 253503. The site has a total land area of approximately 32 Ha. The extent of the site is presented in **Figure 1**.




Figure 1: Site Location (Courtesy of Nearmap)



4.2. Development Site

The total Site area is approximately 32 Ha and is currently rural in use, comprising of dwellings, sheds, dams and grassed fields. The Site is partially bordered by Aldington Road to the west and existing rural lots to the west, north, south and east.

The Site has a general fall from the east to west towards Abbotts Road with existing levels ranging from RL92.5 in the south east, RL 87.5 in the north-east, RL 58.5 in the north west and RL51.0 in Abbotts Rd and Aldington Rd intersection.

There is an external catchment approximately 1.21 Ha entering the northern boundary of the site. An external catchment of approximately 8.2 Ha is entering the eastern boundary of the site. Refer to Figure 2 for external catchment locations.




Figure 2: Extent of external catchments

The Site can be categorised as undulating rural land with several key constraints, including:

- the relatively steep slopes
- lack of existing services



rural road access

There is little or no significant vegetation on the site apart from trees that have been planted and grown around the existing dwellings.

Most of the site is used for general farming activities which appear to be ongoing. There is a potential for low-level pesticide and herbicide contamination which would need to be investigated by the relevant specialist.



Figure 3: Site View from Aldington Rd Abbotts Rd Intersection (Google Street View)

The development site is proposed to be cleared of all the existing built form, dams de-watered and filled, with earthworks to be undertaken across the Site to provide for flat benched platforms. Road and associated infrastructure are proposed to be constructed to services the developed platforms.

External services infrastructure required to service the Site include water main, sewer main, lead-in electrical and NBN.

4.3. Scope and Staging

The scope of this report is to provide the findings of the master planning that has been undertaken to establish the ideal layout for the site. The report summarises the following outcomes:

- Potable water and sewer connections
- Electrical connection points to supply the site
- External access requirements
- Earthworks strategy, retaining walls and boundary conditions
- Stormwater infrastructure requirements
- Estimate of costs for the development and assumptions

Investigations of the Site were carried out based on:

- Dial Before You Dig (DBYD)
- Sydney Water Hydra System
- Penrith City Council Engineering Design Specification
- Penrith City Council Stormwater Drainage Specification



- LIDAR Survey information
- Land Partners Survey
- Sydney Water South West Growth Servicing Plan 2017-2022



Figure 4: Proposed Estate Plan (nettleton tribe)



5. Earthworks

5.1. Existing Geology

Based on the Preliminary Geotechnical Investigation undertaken by Douglas Partners (reference: 92352.00, dated August 2019) for 59-63 Abbotts Road and the Geotechnical Investigation Report prepared by Alliance Geotechnical (reference: 9687-GR-1-1, dated October 2019) for 290-308 Aldington Road, the following inferred sub surface soils were encountered across the site:

- TOPSOIL / topsoil filling to depths of 0.1 0.6m
- FILL to depths of 2.3m over parts of the site
- Residual Soil variably stiff to hard silty clay, to depths in the range 2.5-3.5m
- BEDROCK initially extremely low to very low strength shale or sandstone at first contact at depths of 0.7

5.2. Proposed Earthworks

The site in its existing condition is characterised by undulating topography. It is the intent of the proposed development to produce several "flat" pads to facilitate the development of large-scale industrial lots. This will require earthworks across the site to achieve a benched site, refer to Appendix A for a cut/fill plan.

The cut / fill requirements within the site have been defined through multiple iterations and careful consideration of the following:

- Undulating topography within the Aldington Road Precinct resulting in the requirement for extensive cut and fill operations to allow ESR Development to facilitate economic development and provide flexibility to cater for the range of industrial customer requirements.
- Provisioning for connectivity to adjoining lands and managing existing upstream catchment flows.
- Avoiding retaining walls fronting Aldington Road and mitigating retaining walls fronting internal public road reserves.
- Mitigate extensive cut in bedrock sub-surface units.
- Meet the requirements for the site to cater for IN1 General Industrial employment which requires large flexible allotments.

It is recommended that the proposed earthworks design contained within the AT&L documentation provides the most contextually and economically appropriate design in consideration of the above requirements. Whilst retaining walls fronting Abbotts Road have been avoided as much as possible, this has resulted in a maximum 10m high fill retaining wall along a section of the southern site boundary due to existing topography.

Refer to Drawing 19-609-C1030 for Bulk Earthworks Cut/Fill Plan within Appendix A. Net export is the value highlighted in bold in **Table 3** below.

Table 3: Summary of proposed cut and fill volumes across the site

Item	Volume (m ³)
Stripping of existing topsoil	- 65,700
Excavation of existing creeks and dams (to be exported from site)	- 10,500
Net Cut (including topsoil stripping)	- 709,300
Net Fill	+ 685,800
Balance	- 23,500 (export)

Note these volumes are based on the current design, further detailed design may alter these. – (Negative) balance indicates net cut whilst + (positive) balance indicates import required. It is assumed that all topsoil from the site will be re-used on site as per the specification of the Geotechnical Engineer. Excess topsoil will be exported as required.

The cut and fill volumes presented above have been calculated based on the following assumptions:

- 200mm depth of topsoil stripping over the entire site.
- Any topsoil stripped from the site can be blended in with cut material to be reused based on our experience on similar sites within the vicinity and will therefore not need to be exported off site. This will need to be confirmed by a Geotechnical Engineer at the detailed design phase.

All import materials will comply with the requirements of the requirements of the Import Fill Protocol and Geotechnical Specifications for the Development. Topsoil stripping, blending and placement will be completed in accordance with the Geotechnical Engineering Specifications for the project.



6. Sedimentation and Erosion Control

6.1. Sedimentation and Erosion Control (Construction)

A Soil and Water Management Plan (SWMP) has been prepared in accordance with the NSW Department of Housing Publication titled: Managing Urban Stormwater – Soils and Construction (2004) for the whole site.

The key objectives of the SWMP are:

- Acknowledging the activities on a construction site which may contribute to erosion, sedimentation and water quality impacts.
- The implementation of industry best management practices to minimise adverse water quality and sedimentation impacts brought about through construction activities on waterbodies surrounding the work.
- Establishment of processes that effectively manage erosion, sedimentation and water quality practices during the life of the project.

6.1.1. Sources of Pollution

The activities and aspects of the works that have potential to lead to erosion, sediment transport, siltation and contamination of natural waters include:

- Earthworks undertaken immediately prior to rainfall periods.
- Work areas that have not been stabilised.
- Extraction of construction water from waterways during low rainfall periods.
- Clearing of vegetation and the methods adopted, particularly in advance of construction works.
- Stripping of topsoil, particularly in advance of construction works.
- Bulk earthworks and construction of pavements.
- Works within drainage paths, including depressions and waterways.
- Stockpiling of excavated materials.
- Storage and transfer of oils, fuels, fertilisers and chemicals.
- Maintenance of plant and equipment.
- Ineffective implementation of erosion and sediment control measures.
- Inadequate maintenance of environmental control measures; and
- Time taken for the rehabilitation / revegetation of disturbed areas.

6.1.2. Potential Impacts

The major potential impacts on the riparian environment relate to erosion of distributed areas or stockpiles and sediment transportation. Potential adverse impacts from erosion and sediment transportation can include:

Loss of topsoil.



- Increased water turbidity.
- Decreased levels of dissolved oxygen.
- Changed salinity levels.
- Changed pH levels.
- Smothering of stream beds and aquatic vegetation.
- Reduction in aquatic habitat diversity.
- Increased maintenance costs.
- Decrease in waterway capacity leading to increased flood levels and durations.

6.2. RUSLE Analysis

Prior to the design of the SWMP, a Revised Universal Soil Loss Equation (RUSLE) has been undertaken in accordance with the "Blue Book". This analysis has been undertaken to predict the long term, average and annual soil loss from sheet and rill flow from the site under specified management conditions.

Estimating soil loss for a proposed development has four important applications to soil and water management. These are to:

- 1. Assess the erosion risk at a site.
- 2. Identify suitable measures to overcome the erosion risk.
- 3. Estimate the required capacity of sediment retarding basins.
- 4. Compare the effectiveness of various erosion control measured.

Refer to **Table 4** below for estimates of soil loss on the site.

Table 4: RUSLE Analysis

Parameter	Item (Blue Book Reference)
Rainfall Erosivity Factor, R	1,897.10
Soil Erodibility Factor, K (Table C20, Blue Book)	0.05
Slope Length/Gradient Factor, LS	1.19
Erosion Control Practice Factor, P	1.20
Ground Cover and Management Factor, C	1
Computed Soil Loss (tonnes/ha/year), (A = R x K x LS x P x C)	135.45
Soil Loss Class	1 (Table 4.2)

It should be noted the following parameters/assumptions were used for the analysis of this site:

- Rainfall Erosivity Factor (R) = 2,413.51 from (Equation 2, Appendix A2 Blue Book).
- Soil Erodibility Factor (K) = 0.05 (from Appendix C, Table C19 of Blue Book).



- Slope Length (LS): Is assumed to not exceed 80m immediately before forecast rainfall or during shutdown periods and a maximum grade of 5%.
- Erosion Control Factor (P): Is the ratio of soil loss with a nominated surface condition ploughed up and down the slope (from Appendix A5, Blue Book); and
- Cover Factor (C): Is the ratio of soil loss from land under specified crop or mulch conditions to the corresponding loss from continuously tilled, bare soil. With the proposed ESC measures being installed post bulk earthworks, it is assumed that all soil is recently disturbed, thus a C factor of 1 is chosen.

Erosion hazard	Calculated soil loss (tonnes/ha/yr)	Soil Loss Class	
very low	0 to 150]	
low	151 to 225	2	
low-moderate	226 to 350	3	
moderate	351 to 500	4	
high	501 to 750	5	
very high	751 to 1,500	6	
extremely high	>1,500	7	

Figure 5: Table 4.2 from the Blue Book

The erosion hazard potential of the site is considered very low, due to the calculated soil loss lying in the range of 0 to 150 tonnes/ha/year as per Table 4.2 of the Blue Book.

6.3. Soil and Water Management Plan

6.3.1. Overall Strategy

The following construction methodology will be followed to minimise the impact of sedimentation due to construction works:

- Diversion of "clean" water away from the disturbed areas and discharge via suitable scour protection.
- Provision of hay bale type flow diverters to catch drainage and divert to "clean" water drains.
- Diversion of sediment-laden water into temporary sediment control basins to capture the design storm volume and undertake flocculation (if required).
- Provision of construction traffic shaker grids and wash-down to prevent vehicles carrying soils beyond the site.



- Provision of catch drains to carry sediment-laden water to sediment basins.
- Provision of silt fences to filter and retain sediments at source.
- Rapid stabilisation of disturbed and exposed ground surfaces with hydro-seeding areas where future construction and building works are not currently proposed.
- All temporary sediment basins will be located clear of the 100yr ARI flood extent from South Creek and all associated tributaries.
- The weir levels of temporary sediment basins will be located above the 100yr ARI flood event levels from Ropes Creek and tributaries; and
- Bio-retention basins are to be utilised as temporary sediment control basins. The bio-retention basins shall not be converted into the final/ultimate basins until such time as all building and construction works within the site has been completed and 90% of the site is stabilised.

Refer to AT&L Drawings 20-748-1201 for Erosion and Sediment Control Plans, for all proposed control and protection measures across the site until completion of on lot works.

Suitable temporary erosion and sediment controls shall be designed by a suitably qualified Engineer. Erosion and sediment controls shall be installed and maintained by the Contractor throughout all stages of works. Such controls shall be in accordance with the relevant requirements in the latest version of the managing urban stormwater: soils and construction guideline (Landcom).

6.3.2. Design of Sediment and Erosion Control Measures

Suitable erosion and sediment controls shall be provided by the Contractor and maintained throughout all stages of works, including at completion of the bulk earthworks.

All design, documentation, installation and maintenance of sediment and erosion controls will be in accordance with the requirements of:

- Protection of the Environment Operations Act
- Penrith City Council's guidelines and specifications
- Managing Urban Stormwater: Soils and Construction, Landcom, (4th Edition) (The "Blue Book") Volume 1 and Volume 2

The proposed stormwater detention basin is proposed to be used temporarily as sitewide sediment basin during the bulk earthworks construction. For this approval it has been assumed that the on-lot works will be completed simultaneously, negating the need for individual sediment basins. Ultimately, the final temporary sediment basin locations and sizes will be provided to suit development staging requirements and will be sized and maintained in accordance with the requirements of the above-mentioned authority documents.

With the proposed site being larger than 2,500m2 in disturbed area, sediment basins are required. The following temporary sediment basins are to be in-place at the commencement of demolition works. Refer to drawings in Appendix A and 'Earth Basin Wet' SD6-4 for details, and **Table 5** below for basin sizes.



Table 5: Site Data

Parameter	Item (Blue Book Reference)
Soil Type	Type F (Appendix C, Table C19, Blue Book)
Design Rainfall Depth (Days)	5
Design Rainfall Depth (Percentile)	80
x-day, y-percentile rainfall event (Table 6.3a)	27.4
Rainfall Intensity: 2-year, 6-hour storm	9.93
Rainfall Erosivity (R-factor)	1,897.10

Table 6: Design parameters for estate-wide temporary sediment basin

Parameter	Temporary Sediment basin
Volumetric runoff coefficient	0.5
Area	31.88 ha
80%, 5-day rainfall depth	27.4
Settling zone volume	4368 m ³
Sediment storage volume	2184 m ³
Total sediment volume	6552 m ³

6.4. Site Inspection and Maintenance

The inspection and maintenance requirements outlined in this section must be carried out while either earthworks or quarrying is being conducted, and all areas re-established.

The Contractor will be required to inspect the site after every rainfall event and at least weekly, and will:

- Inspect and assess the effectiveness of the SWMP and identify any inadequacies that may arise during normal work activities or from a revised construction methodology.
- Construct additional erosion and sediment control works as necessary to ensure the desired protection is given to downstream lands and waterways.
- Ensure that drains operate properly and to affect any repairs.
- Remove spilled sand or other materials from hazard areas, including lands closer than 5 metres from areas of likely concentrated or high velocity flows especially waterways and paved areas.
- Remove trapped sediment whenever less than design capacity remains within the structure.
- Ensure rehabilitated lands have affectively reduced the erosion hazard and to initiate upgrading or repair as appropriate.
- Maintain erosion and sediment control measures in a fully functioning condition until all construction activity is completed and the site has been rehabilitated.



- Remove temporary soil conservation structures as the last activity in the rehabilitation.
- Inspect the sediment basin during the following periods:
 - During construction to determine whether machinery, falling trees, or construction activity has damaged and components of the sediment basin. If damage has occurred, repair it.
 - After each runoff event, inspect the erosion damage at flow entry and exit points. If damage has occurred, make the necessary repairs.
 - At least weekly during the nominated wet season (if any), otherwise at least fortnightly; and
 - Prior to, and immediately after, periods of 'stop work' or site shutdown.
- Clean out accumulated sediment when it reaches the marker board/post and restore the original volume. Place sediment in a disposal area or, if appropriate, mix with dry soil on the site.
- Do not dispose of sediment in a manner that will create an erosion or pollution hazard.
- Check all visible pipe connections for leaks, and repair as necessary.
- Check all embankments for excessive settlement, slumping of the slopes or piping between the conduit and the embankment, make all necessary repairs.
- Remove the trash and other debris from the basin and riser; and
- Submerged inflow pipes must be inspected and de-silted (as required) after each inflow event.

6.4.1. Sediment Basin Maintenance

As stated in Section 4.3.2 above, the proposed development site contains 'Type F' soils, or soils that contain a significant proportion of fine grained (33% or more of finer than 0.02mm) and require a much longer residence time to settle.

Stormwater within the settling zone should be drained or pumped out within 5 days (design time), if the nominated water quality targets can be met, to the satisfaction of the superintendent. Flocculation should be employed where extended settling is likely to fail to meet the objectives within the 5-day period.

Flocculation is when flocculating agents are applied to the sediment basins causing the colloidal particles to clump into larger units or 'floc' that can either settle in a reasonable time or be filtered.

Refer to Appendix E4 of the Blue Book for flocculation methodologies and manufacturer's instructions for application rates, regarding the proposed sediment basins.

6.5. Conclusion

The erosion control measures proposed for the site will comply with the requirements of Penrith City Council Engineering Guidelines and The Department of Environment, Climate Change and Water (DECC).

The proposed SWMP will ensure that the best management practice is applied to the development site in controlling and minimising the negative impacts of soil erosion.



7. Retaining Walls

Where possible, batter slopes will be provided to accommodate level changes. Where this is not possible retaining walls will be constructed along the road, lots and basins based on the current civil and earthworks design. A keystone product or other similar face block will be adopted for all retaining walls and will be detailed on the civil drawings. Refer to **Figure 6** to **Figure 8** inclusive for images of the proposed retaining walls.

The proposed retaining walls will be built to the manufacturers design guideline requirements and verified by a structural engineer prior to construction. This practice has previously been adopted other developments within the Penrith City Council LGA and considered input from the geotechnical engineer, utility coordination as well as entry and exit points from proposed lots.

'Boulder' retaining walls are considered another potential retaining wall option for the site. Potential locations of 'boulder' walls will be identified during the detailed design. The walls will be designed and constructed to the structural engineer's specification. Refer to **Figure 9** for an example of the potential "boulder" retaining wall.

Retaining is required along the north, east, and southern site boundary where the proposed building pad levels will be altered from existing levels. Refer to Drawing 20-748-C1080 for cut and fill wall locations. Retaining walls will be designed and constructed using standard industry practices.

All retaining walls will be constructed on a staged basis and as required to suit the development earthworks and stormwater basin works. Where the walls are not constructed a batter of 1 in 4 will be maintained for stability purposes. Any batter steeper than 1 in 5 shall be vegetated.

All retaining walls will be located within private property and not within the road reserve areas, unless within drainage easements.

All retaining walls will have pedestrian and vehicular safety barriers (if required) in accordance with Austroads Guidelines as required.




Figure 6: Typical retaining wall section



Figure 7: Example of retaining wall in location of fill adjacent to road reserve



Figure 8: Example of retaining wall in location of cut



Figure 9: Tiered boulder retaining wall



8. Road Design


8.1. Horizontal and Vertical Geometry

The existing Aldington Road could be classified as a rural road. It currently has a 6-8 metre wide sealed pavement with tables drains on either side within a 20.1m road reserve (refer to **Figure 10**).



Figure 10: View of Aldington Road looking north from Abbotts Road

Aldington Road upgrade has generally been designed to meet Austroads requirements and Australian Standards to accommodate B-Double truck movements. It is expected that Aldington Road will adopt a similar cross-section to that shown below in **Figure 11** when upgraded. With this in mind, we expect a 30.6m wide reservation to be considered along the frontage of the site for the future widening.







See drawings within Appendix A for proposed Road layout.

Subject to Council Approval, it is anticipated that works will need to be undertaken on Aldington Road for the frontage of the site.

The following works are anticipated:

- Access the site via an upgraded intersection at Mamre and Abbotts Road to RMS requirements. This
 intersection upgrade is an interim design and is not intended to accommodate the future Mamre
 Road upgrade mentioned above.
- Abbotts Road and Aldington Road are proposed to be upgraded from Mamre Road and the site generally as shown on Sections 1 & 2 on dwg 20-748-C1010.
- Aldington Road fronting the site will be upgraded generally as shown on dwg 20-748-C1010.

Access to the site is proposed to be via 3-way junction at the Abbotts Road and Aldington Road intersection sized to cater for B-Doubles. The layout provided is intended to be constructed in the interim until the final Aldington Road upgrade is completed by others. The layout provided is contained wholly within the existing road reserve negating the need for adjacent owner's consent. An indicative future road and intersection layout had been provided on plan for context only. Refer to plans 20-748-C1041 and 20-748-C1042.

8.2. Internal Road Network

The internal road network will be designed and constructed in accordance with the Penrith City Council design and construction specifications.

Cul-de-sacs will also be designed and constructed in accordance with the Council guidelines requiring a 16.5m radius on the turn heads.

The Design vehicle is to be a B-Double with a design speed of 60km/hr in the estate roads (extension of Abbotts Road) and 80km/hr on Aldington Road (subject to Council/RMS Approval).

The current Penrith City Council DCP requires a 20.6m wide road reserve to be established. The proposed road reserve has been increased in line with precinct wide discussion and provides a shared path within one of the dedicated verge areas as requested by Penrith City Council. The overall width of the road reservation and following widths for the estate road (Abbotts Road) has been utilised for the site.

The proposed typical ESR Developments Estate Road (Abbotts Road) is designed as such:

Estate Road (extension of Abbotts Road) – refer to Figure 12:

- 24.0m wide Road Reserve
- 15.0m wide Carriageway comprising:
 - 2 x 3.5m wide traffic lanes
 - 2 x 4.0m wide parking lanes adjacent kerb



- Verge 1 at 4.0m wide containing a 1.5m footpath and verge 2 at 5.0m wide containing a 2.5m shared path
- Cul-De-Sac have been shown at 33m diameter to accommodate the largest design vehicle
- The largest design vehicle is a B-Double
- Design Speed of Road = 60km/hr
- No guard fences have been shown or are envisaged at this stage, though these will be assessed at detailed design stage in accordance with Austroads.




Figure 12: Typical Section of the proposed upgrade of Abbotts Road

8.3. Pavement

Pavement will be designed based on the requirements of Austroads Pavement Design Guide – A Guide to the Structural Design of Road Pavements and recommendations provided by Douglas Partners and Alliance Geotechnical reports submitted as part of this SSDA.

The basis of this design is:

- Design Traffic Loading: N =1x10⁷ ESA (in accordance with Penrith City Council requirements for Heavy Industrial)
- Design subgrade CBR = 2% (based on Section 6.7.1 of the Douglas Partners and Alliance Geotechnical Reports)

Based on these parameters the indicative pavement design is as follows:

- 70mm AC 14 320 Bitumen
- 7mm Spray Seal
- 250mm DGB 20 (placed in two layers)
- 500mm Select Sandstone Fill with minimum CBR = 35% (placed in three layers)

If the subgrade CBR = 5% the bottom 200mm of select sandstone fill can be replaced with select fill with minimum CBR of 5%.

CBR testing is proposed to be undertaken at the subgrade level to confirm this pavement design. Polymer modified asphalt will be used within all cu-de-sacs with the asphalt concrete layer becoming a 75mm thick polymer modified AC14.



8.4. Batter Design

Any permanent batters steeper than 1 in 5 will be vegetated in accordance with Penrith City Council requirements. All external batters to the development have been limited to 1 in 4 as a minimum generally, with the maximum localised batter being 1 in 3.

Any temporary batters constructed during the works will be in accordance with the geotechnical report and ongoing advice from the Level 1 supervisor.

8.5. Conclusion

All road design as demonstrated above is in accordance with Austroads Standards and the requirements of Penrith City Council, as a minimum.

A professional geotechnical engineer will be engaged to design the structural pavement. This will be in accordance with *Austroads Pavement Design Guide – A Guide to Structural Design of Road Pavements*.



9. Stormwater Management

9.1. Existing Site Stormwater Drainage

Refer to 20-748-C1061 for a pre-development stormwater catchment plan.

Currently the site comprises rural land and is classified as a "greenfield" site with an entire coverage of pervious areas and farm dams.

The existing site is approximately 32Ha in area with internal catchments falling to the north, east, south and west. There are external catchments entering the site from the northwest corner and eastern boundary of the proposed development with an area of area of 9.41Ha.

There is no existing formal stormwater infrastructure along Abbotts Road and Aldington Road. The site has limited pit and pipe infrastructure to drain the existing site and discharges into Abbotts Road verge. The high point of the site is located on the south eastern side of the site and ranges from approximately RL 88.0m to RL 91.0m. Subsidiary high points on site are in the north eastern corner of the site. Most of the site flows towards the western boundary in the direction of Abbotts Road.

Under existing conditions, stormwater runoff drains across the site via natural swales and farm dams.

Note for the analysis of the pre-development flow rates all dams on the site are assumed to be full, with no allowance for any inherent retention or water quality benefit.

9.2. Proposed Site Stormwater Drainage

Refer to drawing 20-748-C1065 for the proposed catchment plan.

The proposed drainage network has been designed to safely convey major and minor flows within the site prior to discharging towards Abbotts Road. Design rainfall intensities for the proposed drainage network have been adopted as follows:

- Minor System (pits and pipes / culverts): 5% AEP
- Major System (overland flow paths and channels): 1% AEP

The site is mainly a single catchment originating from the north, east and southern boundaries and flowing towards the western boundary where a proposed OSD basin will be located (refer to **Figure 13**).




Figure 13: Location of proposed basin

The proposed on-lot stormwater infrastructure will drain to the stormwater network within the road reserve. The road pit and pipe network will connect to an estate-based On-Site Detention (OSD) basin located in the eastern corner of the site. The proposed OSD basin will have an outlet structure to drain into a pipe system that will discharge in a westerly direction towards the existing gully under Mamre Road. For storm events exceeding the 1% AEP event, the OSD basin will utilise an overflow weir system to drain overland on the neighbouring lot to the west, mimicking the existing overland flow paths onsite. Appropriate flow dissipation will be utilised to control the flow depth and velocity.

A new pipe system is anticipated in the existing Abbotts Road verge downstream of the site, which will convey treated runoff from the proposed bio-retention basin. The pipe is to be located wholly in the existing verge and coordinated with the final design of the upgrade of Abbotts Road. As the pipe will be located in the existing road reserve, it is not anticipated that the adjacent landowners' consent would be required. The pipe system will be combined with the flows from the external catchments located along the eastern boundary and conveyed west towards Mamre Road. The system will discharge overland to a



piped road crossing under Mamre Road. Eventually, when the stormwater system is completed on the upgrade to Mamre Road, the outlet from the basin will connect into this infrastructure.

Refer to the Civil Drawings 20-748-C1041 to 20-748-C1047 for layout and details for the proposed catchments as well as the stormwater network across the site.




Figure 14: Location of Proposed Pipe System to Carry Stormwater Discharge from ESR Development

9.2.1. External Upstream Stormwater Drainage

Part of the overall stormwater strategy for the site involves conveying stormwater flows generated from upstream catchments.

The eastern external catchments will be conveyed via a separate pipe system through the Abbotts Road extension and will be combined with the discharge pipe from the bio-retention basin. As per AT&L drawing 20-748-C1065, the external upstream catchment is located on the eastern boundary of the site. Currently, this catchment sheet flows overland into the site in a westerly direction and discharges to the gully adjacent to Abbotts Road. The total size of the eastern external catchment is 8.2Ha.

The northern external catchment will be conveyed via a separate pipe system along the northern site boundary and into the Aldington Road proposed drainage line. This drainage line drains to the south into the existing piped road crossing at the intersection of Aldington Road and Abbotts Road. As per AT&L drawing 20-748-C1065, the external upstream catchment is located adjacent to the northern boundary of the site. It drains in a southerly direction and discharges into the existing piped road crossing at the



intersection of Aldington Road and Abbotts Road. The total size of the northern external catchment is 1.2Ha.

The impacts on the stormwater design from combining the external catchment flows with the internal site drainage is to be explored in the detail design of the works and an external drainage strategy confirmed prior to issue of construction certificate.

9.3. Stormwater Management Design Criteria Requirements

Design criteria and requirements for the proposed site stormwater management and stormwater drainage are outlined in the following documents:

- AS 3500.3 Plumbing and drainage Stormwater drainage
- Commonwealth of Australia (Geoscience Australia), *Australian Rainfall and Runoff: A guide to flood estimation*, 2019.
- NSW Department of Planning, Industry and Environment (DPIE), Mamre Road Precinct, DRAFT Development Control Plan, November 2020. NB: this document has yet to be finalised and adopted by the NSW DPIE.
- Penrith City Council, *Design Guidelines for Engineering Works for Subdivisions and Developments*, as amended 20 November 2013.
- Penrith City Council, Penrith Development Control Plan 2014, Part C3 Water Management.
- Penrith City Council, Water Sensitive Urban Design (WSUD) Policy, December 2013.
- Penrith City Council, WSUD Technical Guidelines, Version 4 October 2020.

9.4. Stormwater Management Strategy Objectives

The main objectives pertaining to the management of stormwater associated with the proposed development are as follows:

- Stormwater Quantity Management:
 - To ensure post-development peak flow rates do not exceed the pre-development peak flow rates for a range of design storm frequencies and durations, up to and including the 1% AEP design event.
 - To demonstrate how the proposed site design and WSUD measures contribute to the interim NSW Government stormwater catchment flow objectives for the Wianamatta-South Creek catchment, such that the combined effect of site design and site WSUD measures (including on-lot, on street and end of pipe measures) shall contribute no more than 1.9 ML/ha/year in mean annual runoff at any discharge point.
- Stormwater Quality Management:
 - ➤ To provide a stormwater treatment train to satisfy pollutant reduction targets outlined in the Mamre Road Precinct Draft DCP (NB: pollutant load reduction targets in the Draft DCP are significantly higher than those adopted in Penrith City Council's WSUD Technical Guidelines).
- Stormwater Drainage and Flooding:
 - To provide a stormwater drainage system that complies with Penrith City Council design guidelines and specifications.
 - ▶ Finished Floor Levels (FFL) of proposed buildings within the precinct shall have a minimum 500mm freeboard to 1% AEP overland flows.



- Stormwater harvesting and reuse:
 - To install rainwater tanks to meet 80% of non-potable demand including outdoor use, toilets, and laundry (refer to Section 10 of this report for a more detailed description on rainwater harvesting tanks).

The objective to control mean annual runoff volume (MARV) from the site to no more than 1.9 ML/ha/year will require measures to capture and store stormwater runoff in excess of those typically required to satisfy development controls contained in the *Penrith DCP 2014*. Such measures, as outlined in the *Mamre Road Flood, Riparian Corridor and Integrated Water Cycle Management Strategy* (Sydney Water, October 2020), could include:

- Rainwater reuse
- Street tree pits
- Permeable pavements
- Estate-wide irrigation
- Estate-based evaporation ponds
- Wetlands
- Evaporative roof misting

9.5. Stormwater Management Strategy Overview

The proposed stormwater management strategy for the site has been prepared based on an Estate Plan prepared by nettleton tribe (acting on behalf of ESR).

Discussions with ESR established that there is a general preference for achieving stormwater quality objectives through the implementation of end-of-line (estate-wide) stormwater treatment measures, as opposed to at-source (on-lot) measures.

The proposed stormwater quality management strategy for the site has been developed to incorporate the following key measures:

- A gross pollutant trap (GPT) to capture and treat low flow (nominally between the 4 EY and 1 EY design events).
- A bio-retention system to provide secondary treatment of stormwater runoff from the site.

To address Penrith City Council's development controls relating to water conservation, rainwater tanks shall be installed to meet at least 80% of non-potable demand such as outdoor use (irrigation), toilets and laundry.

OSD is required within the development to attenuate post-development flows to pre-development flow rates for a range of design storm events up to and including the 1% AEP event. The required OSD will be incorporated into an estate-wide basin at the downstream end of the site adjacent to Abbotts Road. The OSD basin will incorporate a multi-stage outlet to provide the required stormwater detention volume and to limit discharge such that post-development peak discharge rates do not exceed pre-development peak discharge rates.



As a minimum, the proposed OSD basin will comply with the requirements outlined in the *Penrith City Council Stormwater Drainage Guidelines for Building Developments*.

To comply with the MARV control outlined in the *Mamre Road Flood, Riparian Corridor and Integrated Water Cycle Management Strategy* (Sydney Water, October 2020), additional stormwater management measures will be needed over and above those needed to satisfy the typical (business as usual) stormwater quality and quantity management measures. The measures that have been adopted in the Stormwater Management Strategy for the ESR development site are summarised in **Table 7**:

Measure to achieve MARV control	Adopted in this strategy	Justification
Rainwater reuse	Yes	Can be incorporated into building design with minimal impact on development.
		Rainwater tanks required to satisfy Council DCP performance criteria for non-potable water demand.
Street tree pits	No	Relatively low benefit cost ratio in terms of reduction in mean annual runoff.
Permeable pavements	No	Heavy duty pavements surrounding warehouse buildings are likely to be required to accommodate future tenants (i.e., not conducive to permeable pavements).
		Permeable pavements could be adopted in car parks but would comprise a relatively small proportion of overall impervious area.
Evaporative roof	Yes	Considered an effective measure to reduce runoff from the site.
misting		Relatively high benefit cost ratio in terms of reduction in mean annual runoff.
		Relatively low impact on the Estate Plan layout compared to other measures.
Estate-based evaporative ponds	Yes	Rainwater reuse and evaporative roof misting not sufficient to meet MARV target of 1.9 ML/ha/yr.
Wetlands	No	Higher maintenance cost than an evaporative pond.
		Stormwater quality management primarily provided by means of bio-retention.

Table 7: Additional stormwater management measures to satisfy MARV requirement

9.6. Stormwater Management System Modelling

9.6.1. Hydrological and Hydraulic Modelling

DRAINS modelling software has been used to calculate the Hydraulic Grade Line (HGL) of the estate stormwater pipes. DRAINS is a computer program used for designing and analysing urban stormwater drainage systems and catchments. It is widely accepted by Council's across NSW as the basis for



stormwater design and has been confirmed by Penrith City Council as the preferred stormwater software analysis package. DRAINS data files and output results are attached in Appendix B.

9.6.2. Hydrological and Hydraulic Design Parameters

- Minor system (pit and pipe) drainage shall be designed to accommodate the 5% AEP storm event.
- The combined piped and overland flow paths shall be designed to accommodate the 1% AEP storm event.
- Where trapped low points are unavoidable and potential for flooding private property is a concern, an overland flowpath capable of carrying the total 1% AEP storm event shall be provided. Alternatively, the pipe and inlet system may be upgraded to accommodate the 1% AEP storm event.
- Rainfall intensities have been adopted using the Bureau of Meteorology Design Rainfall Data System (2016).
- Times of concentration for each sub catchment shall be determined using the kinematic wave equation.
- The width of flow in the gutter shall not exceed 2.5 metres and pits shall be spaced no further than 75 metres apart.
- Velocity x depth product shall not exceed 0.4 m²/s for all storms up to and including the 1% AEP event.
- Bypass from any pit on grade shall not exceed 15% of the total flow at the pit; and
- Blockage factors of 20% and 50% shall be adopted for on-grade and sag pits respectively, with these blockage factors in-built to each pit within the DRAINS model.
- A hydraulic grade line HGL design method shall be adopted for all road pipe drainage design.
- Pipelines in roadways shall have a minimum diameter of 375mm.
- A desirable minimum grade of 1% for all pipelines is preferred for self-cleansing under low flow velocities.
- The minimum cover over pipes shall be 450mm in grassed areas and 600mm within carriageways.
- Where minimum cover cannot be achieved due to physical constraints the pipe class shall be suitably increased.
- All pipes in trafficable areas shall be Reinforced Concrete Pipes or Fibre Reinforced Cement equivalent.
- Structural design for all stormwater pits and pipes shall be designed for the ultimate service loads and where applicable, construction loads will be designed for.
- Pipes discharging to the overland flow path shall adopt a minimum tailwater level equivalent to respective overland flow level.
- Pit Loss coefficients shall be calculated in accordance with Missouri Charts.
- A minimum 150mm freeboard shall be maintained between pit HGL and pit surface levels for the minor design storm event (5% AEP).
- Overland flowpaths shall maintain a minimum of 300mm freeboard to all habitable floor levels; and
- Pits deeper than 1.2m shall contain step irons at 300 mm centres.



9.6.3. Water Quality Modelling

The Model for Urban Stormwater Improvement Conceptualisation (MUSIC, Version 6.3.0) was used to evaluate pollutant loads from each of the proposed lots for Post-development (treated) conditions based on the proposed site development. A conceptual view of the MUSIC model used in this report can be found in Appendix C.

Pluviometer data (six-minute rainfall intensity and evapotranspiration) for Penrith Lakes AWS (Station 67113) was used in the MUSIC model. Other parameters that need to be nominated in the MUSIC model (soil characteristics, pollutant event mean concentrations (EMCs)) are consistent with those outlined in the *NSW MUSIC Modelling Guidelines* (August 2015) and the Penrith City Council *WSUD Technical Guidelines* (June 2015).

MUSIC model input parameters for these catchments including rainfall-runoff, base flow concentration and stormflow concentration parameters were selected as per. The parameters used for the various catchment areas are presented in **Table 8** to **Table 11** inclusive.

Parameter	Unit	Value
Rainfall Threshold	mm/day	1.40
Soil Storage Capacity	mm	105.00
Initial Storage	% of Capacity	30.00
Field Capacity	mm	70.00
Infiltration Capacity Coefficient α	-	150.00
Infiltration Capacity Coefficient β	-	3.50
Initial Depth (Ground Water)	mm	10.00
Daily Recharge Rate	%	25.00
Daily Baseflow Rate	%	10.00
Daily Seepage Rate	%	0.00

Table 8: Rainfall-runoff parameters adopted in MUSIC

Table 9: Base Flow/Stormwater Concentration Parameters – Impervious (Roofed) Areas

Pollutant	Baseflow Concentration Parameter – Mean (log mg/L)	Baseflow Concentration Parameter – Std Dev (log mg/L)	Stormflow Concentration Parameters – Mean (log mg/L)	Stormflow Concentration Parameters – Std Dev (log mg/L)
TSS	0.000	0.000	1.300	0.320
ТР	0.000	0.000	-0.890	0.250
TN	0.000	0.000	0.300	0.190



Pollutant	Baseflow Concentration Parameter – Mean (log mg/L)	Baseflow Concentration Parameter – Std Dev (log mg/L)	Stormflow Concentration Parameters – Mean (log mg/L)	Stormflow Concentration Parameters – Std Dev (log mg/L)
TSS	1.200	0.170	2.150	0.320
ТР	-0.850	0.190	-0.600	0.250
TN	0.110	0.120	0.300	0.190

Table 10: Base Flow/Stormwater Concentration Parameters – Pervious Areas

Table 11: Base Flow/ Stormwater Concentration Parameters - Road

Pollutant	Baseflow Concentration Parameter – Mean (log mg/L)	Baseflow Concentration Parameter – Std Dev (log mg/L)	Stormflow Concentration Parameters – Mean (log mg/L)	Stormflow Concentration Parameters – Std Dev (log mg/L)
TSS	0.000	0.00	2.430	0.320
ТР	0.000	0.000	-0.300	0.250
TN	0.000	0.000	0.340	0.190

9.6.4. Catchments

A Stormwater Catchment Plan for each catchment and flow paths into the proposed bio-retention basin is shown in Appendix A. As indicated in the Catchment Plan the basin is to be a bio-retention basin designed to attenuate stormwater flows and treat stormwater pollutants to Penrith City Council target pollutant reduction rates. These treatment rates are from the *Penrith City Council DCP – Section C3 Water Management*.

The overall developed site catchments are as per drawing 20-748-C1065.

A summary of the catchment and the outflow and overflow locations are described below:

Internal Catchments (Lots 01, 02A, 02B, 03, 04, 05, 06, Basin, Café, Roads)

- Total Area = 31.88Ha.
- Flow path to north and east of catchment into the Basin; and
- Outlet flows from the basin to drain to the piped system proposed along Abbotts Road west of the site.
- Overland flow from the basin to discharge overland on the adjacent property located on the west of the ESR development.

External Catchments (A, B, C and D)

Total Area = 9.41Ha.



- Includes external catchments to the north and east of the ESR Development site.
- Flow path to west of catchment via a separate pipe to carry the overland flows from the external catchments.

9.7. Proposed Stormwater Management Measures

A series of stormwater quantity and quality control measures are proposed to be adopted within the ESR Development site to satisfy the stormwater management strategy objectives listed in **Section 9.4**. A general description of the proposed stormwater treatment train components is presented in the following sections.

9.7.1. Rainwater Tanks

Rainwater tanks retain a significant proportion of stormwater that falls on roof areas. Given the largescale industrial development proposed on the site, rainwater tanks can provide a significant contribution to the objective of minimising the total volume of runoff discharging from the site.

A rainwater tank reuse system on individual lots can be installed in many different configurations, including placing the tank above or below ground and using gravity or pressure systems (pumps) to supply rainwater for non-potable domestic uses. These uses typically include toilet flushing, laundry, hot water installations, car washing and irrigation.

Considering rainwater tanks are likely to be fitted with first flush devices, it is likely that they would have minimal water quality benefit. However, they would be required to satisfy the Penrith DCP requirement to meet at least 80% of non-potable demand.

The MUSIC model was developed to estimate the rainwater tank volume required to satisfy the Penrith DCP requirement. To determine the tank volume required to meet at least 80% of non-potable demand on individual lots, the following assumptions have been made:

- Non-potable demand of 0.1 kL/toilet/day has been adopted. The number of toilets within each lot
 has been estimated based on the floor area of warehouses and offices. Fixed daily demands have
 been pro-rated based on the warehouses and offices being occupied six days per week (Monday to
 Saturday).
- Non-potable demand of 2.5 ML/ha/year has been adopted for irrigation of landscape areas on each lot. Irrigation demand has been estimated based on potential evapotranspiration minus rainfall (PET – rain) to account for the likely variability in irrigation demand throughout the year (i.e., high demand in summer, low demand in winter).
- 50% of the total warehouse roof area would drain to the rainwater tank.

A summary of the rainwater tank volumes adopted in MUSIC is presented below in Table 12.



Lot (refer to Estate Plan)	Total Lot Area (ha)	Roof area to rainwater tank ⁽¹⁾ (ha)	Non-potable demand in toilets (kl/day)	Non-potable irrigation demand (ML/year)	Adopted rainwater tank volume (kL)	% of reuse demand met (2)
1	5.10	1.432	2.40	1.32	170	81.9
2a	2.64	0.700	1.20	1.09	120	82.3
2b	2.19	0.500	1.20	1.08	140	81.0
3	5.83	1.583	2.06	1.85	170	81.0
4	5.93	1.535	3.43	3.74	500	81.5

Table 12: Rainwater tank volumes adopted in MUSIC

(1) 50% of total warehouse roof area

(2) From MUSIC model Node Water Balance

9.7.2. Gross Pollutant Traps

The proposed stormwater treatment train would consist of a gross pollutant trap (GPT) as a means of primary stormwater treatment. GPTs are designed to capture litter, debris, coarse sediment, as well as some oils and greases.

A proprietary GPT such as the Ocean Protect OceanSave would be adopted to capture and treat low flows prior to discharge to secondary treatment (bio-retention). The GPT(s) would be located adjacent to the proposed bio-retention / detention basin.

A high-flow bypass for the GPTs would nominally be equivalent to the 4 EY (3-month ARI) peak flow rate discharging to the GPT. Design flows for the GPTs and their final configuration would be confirmed at the detailed design phase.

9.7.3. Bio-Retention Systems

The objective of bio-retention systems is to provide a filtering effect when stormwater runoff flows through a vegetation layer and sand and/or gravel filer media to remove pollutants from the runoff. Bio-retention systems generally consist of an open space containing landscaping of native grasses, shrubs and trees with an underlying filter media.

A bio-retention basin is proposed to be at located adjacent to Abbotts Road and the western boundary of the site. This basin would be constructed to collect surface runoff from roads and industrial lots.

MUSIC model parameters used for the Bio-retention basin were based off guidelines provided by FAWB – Stormwater Biofiltration Systems – Version 1, 2009, and were modified accordingly. Parameters used to model the bio-retention basin are shown in the **Table 13**.



Table 13: Bio-retention basin parameters

Parameter	Unit	Value
Extended Detention Depth	m	0.30
Surface Area	m²	3800
Filter Area	m²	3440
Unlined Filter Media Perimeter	m	0.01
Saturated Hydraulic Conductivity	mm/hour	125
Filter Depth	m	0.50
TN Content of Filter Media	mg/kg	800
Orthophosphate Content of Filter Media	mg/kg	40
Exfiltration Rate	mm/hour	0.00
Base Lined	-	No
Vegetation Properties	-	Vegetated with Effective Nutrient Removal Plants
Overflow Weir Width	m	10.00
Underdrain Present	-	Yes
Submerged Zone	-	No

9.7.4. On-Site Stormwater Detention (OSD)

As discussed in Section 9.1 the site is mainly a single large stormwater catchment with external catchments. The stormwater on the lots and within the road reserve for the overall development of the site is proposed to be collected via pits and pipes and connect into an OSD basin adjacent to the western boundary of the site.

The external catchment runoff will not be detained or treated and will bypass the site's bio-retention basin. It is assumed that any stormwater quantity or quality management that may be required for these upstream catchments would occur on the separate lots at the time of development.

For the post-development case it is proposed to maintain the existing point of discharge and ensure peak flow rates are not increased via the OSD basin. Controlled outlets from the OSD basin will include surcharge pits connected to subsurface drainage pipes (for low flows) and weirs (for high flows). Refer to Drawing 20-748-C1071 & 20-748-C1072 for the OSD basin details.

9.7.5. Estate-wide Ponds

Ponds are considered to provide an effective means of reducing runoff volume from the site as water would be lost via evaporation over a large area. A pond can be relatively cheap to construct with the potential to capture large quantities of stormwater runoff, while also being relatively easy to maintain.



Large-scale MUSIC modelling undertaken by AT&L indicates that, in combination with other measures, ponds can achieve a relatively high reduction of stormwater runoff volume.

A major drawback of estate-wide ponds is the significant portion of developable land that would need to be set aside. MUSIC modelling undertaken of a typical large-scale industrial estate indicates that, to achieve the target of MARV of 1.9 ML/ha/year, around 15% of the total area of an estate would need to be set aside for ponds.

This Stormwater Management Strategy, which addresses the target MARV specified in the *Draft Mamre Road Precinct DCP*, incorporates ponds on proposed Lots 5 and 6. Key parameters adopted for the two ponds are summarised below in **Table 14**.

Parameter	Pond 5	Pond 6		
Inflow from:	Proposed Lots 2b, 3 and 4	Proposed Lot 2a		
		Pond 5		
Outflow to:	Pond 6 Proposed drainage in ext of Abbotts Road			
Surface Area (m ²)	29000	10600		
Permanent Pool Volume (m ³)	54000	18800		
Exfiltration rate (mm/hr)	0	0		
Evaporative loss (% of PET)	75	75		
Outlet (equivalent pipe diameter)	600	375		

Table 14: Adopted pond parameters

9.7.6. Evaporative misting on roof areas

Roof misting is a relatively new and emerging technology that can be used for cooling and dust suppression. It is a method for reducing ambient temperatures inside and outside of buildings that is promoted by the Low Carbon Living CRC (2017) as an urban cooling strategy to reduce the impacts of extreme heat and as a means of reducing stormwater runoff volumes (Sydney Water, 2020).

While a significant water storage is required for each industrial lot, the misting infrastructure is relatively basic and can be incorporated into the final building services design.

To estimate the potential water loss by evaporation for a roof misting system, additional rainwater tanks have been modelled in MUSIC. As per the *Mamre Road Precinct FRCIWCM Report* (Sydney Water, 2020), a notional demand rate of 4.5ML/Nha/yr has been adopted and distributed as a fixed annual demand, variable by PET minus rainfall.



The storage tanks required for roof misting could be amalgamated into rainwater reuse tanks for nonpotable water reuse. For this Stormwater Management Strategy, it is assumed that the rainwater reuse tanks for non-potable water supply would be separate to the tanks for evaporative misting supply.

Due to potential impacts of roof misting systems on the performance of rooftop solar panels, it has been assumed that misting would be applied to no more than 50% of the total warehouse roof area.

Further analysis would be required at the detailed design phase to verify evaporative misting system design parameters such as:

- Extent of roof area that would drain to a rainwater tank installed for the purpose of evaporative misting.
- The available roof area for misting, taking into consideration the cost of misting infrastructure and interface with other infrastructure such as solar panels.
- The impact of an additional pipe network and the corresponding roof weight on the structural design.
- Ongoing maintenance and WHS considerations associated with roof misting infrastructure.

A summary of the rainwater tanks for roof misting adopted in MUSIC is presented below in **Table 15**.

Lot		· · · · · · · · · · · · · · · · · · ·	Adopted	Annual misting demand (ML/year)	MUSIC Node Water Balance Results		
(refer to Estate Plan)	Area (ha)	to roof misting tank ⁽¹⁾ (ha)	roof misting tank volume (kL)		Inflow (ML/yr)	Misting Supply (ML/yr)	Tank Overflow (ML/yr)
1	5.10	1.43	150	6.45	8.46	2.73	5.73
2a	2.64	0.70	150	3.15	4.14	1.85	2.31
2b	2.19	0.50	150	2.25	2.95	1.50	1.47
3	5.83	1.58	150	7.12	9.35	2.85	6.49
4	5.93	1.54	150	6.91	9.07	2.82	6.25

Table 15: Summary of roof misting tank parameters

(1) It is assumed that 50% of the total warehouse roof area would drain to the rainwater tank for roof misting.

9.8. Scenario Modelling

A MUSIC model was created to simulate both the pre-development and post-development scenarios. The pre-development model is a single source node to estimate the mean annual runoff and pollutant loads under existing conditions. The post-development model has been created based upon the land uses depicted in the Estate Plan prepared by nettleton tribe (refer to **Figure 4**). The layout of the post-development scenario is presented in **Figure 15**.

at&l




Figure 15: MUSIC model layout

The land use breakdown for each of the catchments under the post-development scenario is presented in **Table 16**.

Catchment	Total Area (ha)	Warehouse Roof Area (ha)	Office Roof Area (ha)	Hardstand area (ha)	Landscape Area (ha)
Lot 1	5.10	2.87	0.09	1.62	0.53
Lot 2a	2.64	1.40	0.05	0.75	0.43
Lot 2b	2.20	1.00	0.05	0.71	0.43
Lot 3	5.83	3.17	0.10	1.83	0.74
Lot 4	5.93	3.07	0.07	1.29	1.50
Lot 7	0.17	-	0.02	0.04	0.12
Access Road	1.85	-	-	1.85	-

Table 16: Post-development scenario land use breakdown



The post-development scenario model incorporates the following stormwater management measures:

- Rainwater tanks, as per the parameters presented in **Table 12**.
- GPTs, as per the parameters described in Section 9.7.2.
- A bio-retention system, as per the parameters presented in **Table 13**.
- An OSD basin, as per the parameters described in Section 9.7.2.
- Estate-wide ponds on proposed lots 5 and 6, as per the parameters presented in Table 14.
- Evaporative misting using rainwater collected in dedicated tanks, as per the parameters in **Table 15**.

The attributes for each of the proposed stormwater management measures have been determined such that they will satisfy the pollutant reduction targets and MARV target outlined in **Section 9.4**.

9.9. Model Results

9.9.1. MUSIC Model Results

MUSIC modelling results presented as mean annual loads at the receiving node indicate that adopted target reductions are achieved, as shown in **Table 17**.

Parameter	Sources – Pre- Development	Sources – Post- Development	Residual Load – Post- Development	Reduction (%)	Target Reduction (%) – Mamre Road Precinct Draft DCP ⁽¹⁾	Target Reduction (%) – Penrith DCP
Flow (ML/yr)	47.8	122	59.1	51.6	50.2	
TSS (kg/yr)	8720	18700	193	99.0	95	85
TP (kg/yr)	14.2	39.4	3.88	90.2	75	60
TN (kg/yr)	106	275	40.5	85.3	68	45
Gross Pollutants (kg/yr)	49.6	3290	0	100	100	90

Table 17: Summary of MUSIC modelling results

(1) Target flow reduction based on post-development flow calculated in MUSIC (122 ML/yr) and target MARV of 1.9 ML/ha/year * 32 ha = 60.8 ML

9.9.2. DRAINS Model Results

Table 18 presents the pre-development and post development flow rates for all storm events at the outlet of the proposed OSD basins. The OSD within the Basin has been designed to achieve the following outcomes for all pre and post developed cases.



Design Storm Event	Pre-Development Peak Flow Rate (m³/s)	Post Development Peak Flow Rate (m³/s)
1 EY	4.16	2.55
0.5 EY	5.44	2.72
0.2 EY	7.77	2.96
5% AEP	10.8	3.23
1% AEP	14.5	3.51

Table 18: Pre-development and post-development peak flow rates from the proposed development

9.10. Conclusion

As highlighted in the above section all stormwater drainage within the ESR development has been designed in accordance with the Penrith City Council Engineering Guidelines. This includes design of the stormwater network (pits and pipes), On-Site Detention basins and WSUD infrastructure. To summarise:

- OSD has been to be sized to ensure that for all rainwater events up to and including the 1% AEP event, does not increase peak stormwater flows downstream of the site.
- OSD to attenuate post development peak flow rates to less than pre-development flows for a range
 of design storm events.
- WSUD to achieve the target pollutant reductions outlined in the *Draft Mamre Road Precinct DCP*:
 - 95% Total Suspended Solids (TSS)
 - 75% Total Phosphorus (TP)
 - ▶ 68% Total Nitrogen (TN)
 - 100% Gross Pollutants (GP)
- Finished Floor Levels (FFL) to have minimum 500mm freeboard to 1% AEP overland flows.



10. Water Balance

10.1. General

A water balance model was developed using the MUSIC software package to allow the evaluation of various elements of the water cycle to be assessed.

Penrith City Council WSUD policy (July 2015) stipulates that rainwater tanks are required to meet 80% of non-potable demand including outdoor use, toilets and laundry.

10.2. Water Balance Objective

Potable water supplies in the Sydney area are in recognised short supply with projected population increases, potential climate change and periods of extended drought. It is acknowledged that any development in the Sydney region places greater demand on an already limited water supply. As a result, government bodies, together with Sydney Water have encouraged sustainable development by the implementation of an integrated approach to water cycle management (potable water, sewerage, stormwater and rainwater) to minimise potable water demand and maximise the potential for non-potable water sources to replace potable water demand where possible.

Whilst opportunities for water reuse could include initiatives as regional stormwater harvesting, and reticulated recycled water, this development is limited to rainwater harvesting and reuse on an individual lot by lot basis.

As such, we have used MUSIC to establish an estimated tank size for each lot within the development and demonstrated the volume of water reuse possible and provide a more sustainable servicing solution.

10.3. Water Balance End Uses

AT&L has identified the following water demand end uses to be required across the development:

- Toilet flushing (within the proposed warehouse and office developments).
- Landscape irrigation (outdoor garden use).

The proportion of total water demands for irrigation and toilet flushing within the development could be met with the use of recycled roof water drained directly into a rainwater tank. The tank should be sized to ensure the site meets the requirement to meet the 80% non-potable reuse requirement. This is in accordance with Penrith City Council's WSUD policy.

10.4. Total Site Demands and Non-Potable Reuse Rates

The following rates were adopted from the *Penrith City Council WSUD Technical Guidelines* for Industrial and Commercial developments (Section 4.5):

2.5 ML/ha/yr for landscape irrigation (variable by potential evapotranspiration minus rain).



0.1 kL/day per toilet per year for toilet flushing.

10.5. Rainwater Reuse

The use of rainwater collected in rainwater tanks from runoff on the roofs of the warehouse roofs provides a valuable alternative to potable water for a variety of non-potable end uses, such as vehicle washing, air conditioning cooling, and toilet flushing and watering.

It has been assumed for this development that irrigation systems will be plumbed to the rainwater tanks. Other uses of harvested rainwater such as truck washing may be considered at the detailed design stage but would be dependent on the water demands of individual tenants.

A rainwater tank model was constructed to simulate the rainwater tank operations and select the optimal rainwater tank size, in doing so, the following considerations were made:

- Rainfall on the catchment.
- Roof area (it is assumed that rainwater harvesting would be limited to roof areas only).
- Roof wetting.
- First flush; and
- Rainwater demands (by end use).

10.6. Proposed Rainwater Tank Parameters

As presented in **Table 12**, the MUSIC model results demonstrate that rainwater tanks on each of the individual lots can satisfy the Penrith DCP requirement for non-potable water supply throughout the development.

The adoption of rainwater harvesting tanks as part of the site water management strategy, and the design basis to size the tanks to comply with the requirement that 80% of all non-potable water demand on each lot can be sourced from the tank, demonstrates a commitment to water recycling and minimising the usage of potable water throughout the development. This is in line with the industry best practice and the NSW Government's objective of reducing the amount of potable (drinking) water consumed for non-potable uses.



11. Services Investigation

Based on an initial desk top study conducted from information obtained from Dial Before You Dig (DBYD) records, the following utility services are located within the vicinity of the Site:

- Potable water Sydney Water
- Electrical Endeavour Energy
- Telecommunications Telstra

No sewer or gas was noted to be located within the vicinity of the Site.

Investigations of the Site were carried out based on:

- Site inspection
- Dial Before You Dig (DBYD) search
- Sydney Water Hydra System
- Penrith City Council Engineering Design Specification
- LIDAR Survey information
- Sydney Water South West Growth Servicing Plan 2017-2022

11.1. Potable Water

11.1.1. Existing Potable Water

Dial Before You Dig (DBYD) indicates the following water services within the area:

- 100mm diameter CICL potable watermain on the southern side of Abbotts Road
- 150mm diameter DICL potable watermain on the northern side of Abbotts Road
- 180mm diameter uPVC PE on eastern side of Aldington Road.

11.1.2. Proposed Potable Water

Based on our investigations and ongoing discussions with Sydney Water, connection to the Oakdale West infrastructure will be utilised to provide water services to the site is proposed.

As part of the Oakdale West Development (north of the site), a Local Area Servicing Plan (LASP) was prepared and endorsed by Sydney Water which will provide additional trunk water infrastructure for the area. Included within these works is an extension of a 300mm diameter main from Lenore Drive through to Bakers Lane.

Subject to Sydney Water approval and further modelling, it is proposed to extend the above-mentioned 300mm main along Aldington Road to service the Site. The main will be cross connected to the existing water mains and through connected to the existing 2 x 150mm diameter main within Mamre Road. This main will be fully reimbursable subject to SWC approval.



The internal reticulation will consist of either a 200 or 250dia main running along the side of the road. Refer to **Figure 16** below for the proposed potable water services to the site.




Figure 16: Proposed Water Strategy

11.2. Sewer

11.2.1. Existing Sewer

Dial Before You Dig (DBYD) indicates there is no existing sewer infrastructure located at or adjacent to the Site.

11.2.2. Proposed Sewer

The Site is located within the western catchment of Mamre Road Precinct that drains to a proposed wastewater pumping station via proposed trunk wastewater carriers. The pumping station will be required to transfer flows to St Marys wastewater network for interim servicing to 2026 and after this time it is intended for the pumping station to transfer flows south to the proposed Upper South Creek Advanced Water Recycling Centre. This is due to capacity constraints in the St Marys wastewater network:

- Sydney Water planned to start concept design in November 2020, for the wastewater pumping station and carriers servicing the western catchment. Concept design will include environmental approvals, geotechnical investigations, survey, etc.
- The delivery date for servicing the western catchment is planned for 2023/24 and subject to funding approval.



Road Mamre Road Precinct -Trunk Wastewater Interim Servicing Scheme Indicative and subject to route alignment 3 confirmation during concept design. IN1 5 E2 RE1 BAKERS 2 Eastern catchment drains by gravity to St Marvs wastewater system RE RE2 F INT SP2 Western catchments interim pumping as selied to St Marvs wastewater network Road Legend 76 Indicative catchment boundary Indicative pressure sewer area Indicative location of wastewater pumping station - not to scale NORTH SITE Indicative location of 6. trunk gravity mains kilometres Indicative location of Copyright reserved Sydney Water 2020 pressure main No warranty is given that this is complete Existing wastewater mains or accurate

Refer to indicative wastewater servicing plan below.

Figure 17: Indicative Wastewater servicing plan (Sydney Water)

Note - all the assets are in planning stage, indicative and subjected to route alignment confirmation during concept and detailed design. Additional reticulation mains are required to service the development and are required to be sized to service the natural catchment as per the WSAA Code.

If the site is developed in advanced of Sydney Water's proposed works and sufficient infrastructure is not available, an Interim Operating Procedure (IOP) will need to be developed to allow for wastewater to be constructed to service the site. The IOP will need to be raised and will be subject to approval from Sydney Water.

11.3. Electrical

11.3.1. Existing Electrical

Recent site inspection indicates that there is an overhead power line (11kV and 240v) on the eastern side of Aldington Road reserve parallel to the boundary. Dial Before You Dig (DBYD) indicates that there are no underground services within the vicinity of the Site.

11.3.2. Proposed Electrical

Consultation has been undertaken with Endeavour Energy regarding electrical servicing strategies for the Broader Western Sydney Employment Area (BWSEA) which includes the wider Aldington Road Precinct and the Site.

The Endeavour Energy 'Western Sydney Priority Growth Area – Area Plan April 2018' indicates the proposed high voltage network to be delivered as part of the wider Endeavour Energy electrical network required to service the Aerotropolis.

Endeavour Energy's Asset Planning & Performance Branch has provided the following advice:

- Asset Planning & Performance have met with consultants for ESR Kemps Creek Logistics Park and discussed power servicing requirements at an early high-level stage.
- Based on standard warehousing load estimations, the client was advised that a new 11 kV feeder would be required to be established from Kemps Creek Zone Substation located at 120 Cross Street Kemps Creek (Lot 1 DP 532554) to the site to provide the required capacity. This is due to the existing electrical infrastructure in the vicinity having insufficient capacity to support the proposed large-scale development along Mamre Road and Aldington Road with several partial developments involving a number of warehouses which have been processed and allowed to connect.
- This has subsequently resulted in no further spare capacity being available without extensive new capital investment required to provide new capacity in addition to and in advance of the proposed new 132kV / 22 kV zone substation within the Oakdale West Precinct known as South Erskine Park Zone Substation by the current expected commissioning date of October 2022. This substation will service both the Oakdale West and Mamre Precincts and limited parts of the Oakdale South Precinct.
- Developments which are running ahead of Endeavour Energy's infrastructure delivery timeline are being advised to make alternative arrangements to access spare capacity from either Kemps Creek Zone Substation or Mamre Zone Substation located at 8 John Morphett Place Erskine Park (Lot 9 DP 1097134) depending on where they are located until supply can be redirected from the new South Erskine Park Zone Substation. Some warehousing has been accommodated where possible on an interim basis until the new zone substation is available.
- Asset Planning & Performance are happy to meet with ESR to continue conversations regarding the
 provision of capacity ahead of South Erskine Park Zone Substation which may entertain connection of
 one or two warehouses dependent on the load requirement, some infrastructure augmentation is
 still likely to be required due to the rural construction type of existing infrastructure.

Although it was not identified which option would be the most suitable option, Connect Infrastructure has advised that further consultation with Endeavour Energy will be required and based on the risk / reward profile, a suitable option can be determined.

11.4. Telecommunications

Dial Before You Dig (DBYD) indicates that Telstra below-ground conduits are located within the Aldington Road Reserve parallel to the boundary.

Site inspection has identified there are aboveground assets along the western side of Aldington Road.



It is expected connection could be made from the existing infrastructure located within Aldington Road. Subject to the requirements of the relevant telecommunications authority, new pit and pipe may need to be installed from Erskine Park Road to the Site.

11.5. Gas

There are no existing Jemena gas mains located within the vicinity of the Site. No contact has been made with Jemena to determine if there are plans to service the area in future.

11.6. Conclusion

This section demonstrates that services including wastewater, potable water, power, telecommunications and gas can be made available to the site.

Internal reticulation will be coordination at the detailed design stage of works with formal applications made to the relevant service authorities.

at&l

12. Infrastructure Delivery and Staging

12.1. Staging

The estate wide civil infrastructure works will be undertaken within Stage 1 of the development of the site. The infrastructure works will include, but are not limited to:

- Upgrade of Abbotts Road and Aldington Road.
- Extension of Abbotts Road within the development site.
- Earthworks and retaining walls / structures.
- Stormwater drainage systems, including diversion of external catchments through the site.
- Stormwater management measures, including on-site detention and bio-retention systems.
- Utility services (water, sewerage, power, communications), including lead-in works as required.

Stage 1 will include external road upgrades and service lead-in works. The delivery of construction will be undertaken progressively to meet end user requirements.

12.2. Funding Arrangements

The assumed funding arrangement for civil infrastructure works will be as follows:

- Abbotts Road and Aldington Road Upgrades (including roundabout): Proposed to be delivered as Works in Kind Agreement against Section 7.11 and/or Section 7.12 contributions (subject to authority approvals).
- Lead-in services: Proponent funded with potential reimbursements subject to relevant authority approvals and procurement processes.
- Internal works: Proponent funded.


at&

APPENDIX A – Civil Engineering Plans



APPENDIX B – DRAINS Model


at&l





APPENDIX C – MUSIC Results

at&l



Treatment	Train	Effect	tiveness	- Post-D)evelo	pment N	ode
-----------	-------	--------	----------	----------	--------	---------	-----

	Sources		Residual Load		% Reduction	
	Pre	Post	Pre	Post	Pre	Post
Flow (ML/yr)	47.8	122	47.8	59.1	0	51.6
Total Suspended Solids (kg/yr)	8690	18600	8690	195	0	99
Total Phosphorus (kg/yr)	13.9	39.4	13.9	3.88	0	90.2
Total Nitrogen (kg/yr)	105	274	105	40.4	0	85.3
Gross Pollutants (kg/yr)	49.6	3290	49.6	0	0	100




SYDNEY LEVEL 7 153 WALKER STREET NORTH SYDNEY NSW 2060 02 9439 1777 INFO@ATL.NET.AU

BRISBANE SUITE A LEVEL 11 127 CREEK STREET BRISBANE QLD 4000 07 3211 9581 INFO-QLD@ATL.NET.AU

atl.net.au

ABBOTTS ROAD **KEMPS CREEK** CIVIL WORKS PACKAGE STATE SIGNIFICANT DEVELOPMENT APPLICATION



			Bar Scales
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21	
Α	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20	
Issue	Description	Date	

100mm on Original

NTS

Scales Projec PDK Client N.T.S. Designed PDK THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN Checked Grid **GDA94 MGA56** TM ANY FORM OR USED FOR ANY ESR Height Approved AHD **OTHER PURPOSE OTHER THAN** Datum Title THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walke North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 05 77
COVER SHEET	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
	Project - Drawing No. 20-748-C1000	Issue B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1000.dwg

	IST
DRAWING No.	DRAWING TITLE
1000-SERIES INF	RASTRUCTURE
20-748-C1000	COVER SHEET
20-748-C1001	DRAWING LIST
20-748-C1002	GENERAL NOTES
20-748-C1005	GENERAL ARRANGEMENT PLAN
20-748-C1010	TYPICAL ROAD SECTIONS SHEET 1
20-748-C1011	TYPICAL ROAD SECTIONS SHEET 2
20-748-C1020	BOUNDARY INTERFACE PLAN
20-748-C1021	BOUNDARY INTERFACE SECTIONS SHEET 1
20-748-C1022	BOUNDARY INTERFACE SECTIONS SHEET 2
20-748-C1023	BOUNDARY INTERFACE SECTIONS SHEET 3
20-748-C1030	BULK EARTHWORKS CUT\FILL PLAN
20-748-C1041	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
20-748-C1042	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
20-748-C1043	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 3
20-748-C1044	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 4
20-748-C1045	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 5
20-748-C1046	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 6
20-748-C1047	ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 7
20-748-C1050	ABBOTTS ROAD (MC01) LONGITUDINAL SECTION SHEET 1
20-748-C1051	ABBOTTS ROAD (MC01) LONGITUDINAL SECTION SHEET 2
20-748-C1052	ABBOTTS ROAD (MC01) LONGITUDINAL SECTION SHEET 3
20-748-C1055	ALDINGTON ROAD (MC02) LONGITUDINAL SECTION SHEET 1
20-748-C1061	STORMWATER DRAINAGE CATCHMENT PLAN (PRE-DEVELOPED)
20-748-C1065	STORMWATER DRAINAGE CATCHMENT PLAN (POST-DEVELOPED)
20-748-C1071	BIO-RETENTION BASIN DETAIL PLAN
20-748-C1072	BIO-RETENTION BASIN SECTION
20-748-C1080	RETAINING WALL GENERAL ARRANGEMENT PLAN SHEET 1
20-748-C1081	RETAINING WALL GENERAL ARRANGEMENT PLAN SHEET 2
20-748-C1085	RETAINING WALL PROFILES SHEET 1
20-748-C1086	RETAINING WALL PROFILES SHEET 2
20-748-C1087	RETAINING WALL PROFILES SHEET 3
20-748-C1088	RETAINING WALL PROFILES SHEET 4
20-748-C1089	RETAINING WALL PROFILES SHEET 5
20-748-C1090	RETAINING WALL PROFILES SHEET 6
20-748-C1091	RETAINING WALL PROFILES SHEET 7
20-748-C1092	RETAINING WALL PROFILES SHEET 8
20-748-C1093	RETAINING WALL PROFILES SHEET 9
20-748-C1094	RETAINING WALL PROFILES SHEET 10
20-748-C1095	RETAINING WALL PROFILES SHEET 11
20-748-C1101	SERVICES AND UTILITIES COORDINATION PLAN SHEET 1
20-748-C1102	SERVICES AND UTILITIES COORDINATION PLAN SHEET 2
20-748-C1103	SERVICES AND UTILITIES COORDINATION PLAN SHEET 3
20-748-C1201	EROSION AND SEDIMENT CONTROL PLAN
20-748-C1210	EROSION AND SEDIMENT CONTROL DETAILS
20-748-C1311	VEHICLE TURNPATH PLAN SHEET 1
20-748-C1312	VEHICLE TURNPATH PLAN SHEET 2

			Bar Scales
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21	
А	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20	
Issue	Description	Date	
	100mm on Original		

	2000-SERIES ON LOT
20-748-C2111	LOT 01 SITEWORKS AND STORMWATER DRAINAGE PLAN
20-748-C2121	LOT 01 PAVEMENT PLAN
20-748-C2211	LOT 02A & LOT 2B SITEWORKS AND STORMWATER DRAINAGE PLAN
20-748-C2221	LOT 02A & LOT 2B PAVEMENT PLAN
20-748-C2311	LOT 03 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
20-748-C2312	LOT 03 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
20-748-C2321	LOT 03 PAVEMENT PLAN SHEET 1
20-748-C2322	LOT 03, LOT 04 & LOT 5 PAVEMENT PLAN SHEET 2
20-748-C2411	LOT 04 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
20-748-C2412	LOT 04 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
20-748-C2421	LOT 04 & LOT 5 PAVEMENT PLAN SHEET 1
20-748-C2422	LOT 04 & LOT 5 PAVEMENT PLAN SHEET 2
20-748-C2511	LOT 05 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
20-748-C2512	LOT 05 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
20-748-C2521	LOT 05 & LOT 06 PAVEMENT PLAN SHEET 1
20-748-C2522	LOT 05 PAVEMENT PLAN SHEET 2
20-748-C2611	LOT 06 & LOT 07 SITEWORKS AND STORMWATER DRAINAGE PLAN

	Client	Scales	Drawn	PDK	Project PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	
THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN		N.T.S.	Designed	PDK	DEVELOPMENT	Level 7, 153 Walk North Sydney NS	SW 2060
		Grid GDA94 MGA56	Checked	TM	ABBOTTS ROAD	ABN 96 130 882 4 Tel: 02 9439 1 Fax: 02 9923 1	1777
		Height Datum AHD	Approved		KEMPS CREEK	www.atl.net.au info@atl.net.au	
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					DRAWING LIST	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
						Project - Drawing No. 20-748-C1001	Issue R
						SSDA\1000_INFRASTRUCTURE\20-748-C1001	1 dwg

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1001.dwg

SITEWORKS NOTES

- 1. ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE **REPORTED TO AT & L.**
- 3. MAKE SMOOTH CONNECTION WITH EXISTING WORKS.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMAPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO R.M.S SPECIFICATION R116.
- 8. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051 (UNBOUND), R.M.S FORM 3052 (BOUND) COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m OF BASECOURSE MATERIAL PLACED.
- 9 ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051, 3051.1 AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2. FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH R.M.S FORM 3051 AND 3051.1 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF AT & L.
- 11. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THE CONTRACTOR IS TO SEEK ACCEPTANCE OF THE PRODUCT FROM AT&L. THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED
- 12. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

SURVEY NOTES

THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY LTS LOCKLEY, BEING

REGISTERED SURVEYORS. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. AT & L DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS.

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT AT & L.

THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM THE ORIGINAL SURVEY DOCUMENTS.

NOTES

- 1. THE BOUNDARIES HAVE APPOROXIMATELY BEEN SURVEYED IN ACCORDANCE WITH CLAUSE 9 OF THE SURVEYING & SPATIAL INFORMATION **REGULATION 2017**
- 2. ALL AREAS AND DIMENSIONS HAVE BEEN COMPILED FROM PLANS MADE AVAILABLE BY NSW LAND REGISTRY SERVICES AND ARE SUBJECT TO FINAL SURVEY
- 3. ORIGIN OF COORDINATES HAS BEEN DERIVED USING GPS (GNSS) SURVEY FROM SSM33562
- 4. ORIGIN OF LEVELS ON A.H.D. IS TAKEN FROM SSM33562 R.L. 43.021 (A.H.D.) MAMRE ROAD USING GPS (GNSS) SURVEY METHODS. IN 5. CONTOUR INTERVAL 0.5 m
- 6. CONTOURS ARE INDICATIVE ONLY. ONLY SPOT LEVELS SHOULD BE USED FOR CALCULATIONS OF QUANTITIES WITH CAUTION
- 7. NO INVESTIGATION OF UNDERGROUND SERVICES HAS BEEN MADE. SERVICES HAVE BEEN PLOTTED FROM RELEVANT AUTHORITIES INFORMATION AND HAVE NOT BEEN SURVEYED, ALL RELEVANT
- AUTHORITIES SHOULD BE NOTIFIED PRIOR TO ANY EXCAVATION ON OR NEAR THE SITE 8. 8/.4/7 DENOTES TREE SPREAD OF 8m, TRUNK DIAMETER OF 0.4m & APPROX
- HEIGHT OF 7m
- 9. SHOWS APPROXIMATE POSITION OF ROAD LINEMARKING AND IS INDICATIVE ONLY
- 10. BEARINGS SHOWN ARE MGA (MAP GRID OF AUSTRALIA) ADD APPROX. 1°00' FOR TRUE NORTH

CONCRETE NOTES

- 1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- 2. CONCRETE QUALITY ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE UNLESS NOTED OTHERWISE

ELEMENT	AS 3600 F'c MPa AT 28 DAYS	SPECIFIED SLUMP	NOMINAL AGG. SIZE
VEHICULAR BASE	32	60	20
KERBS, PATHS, AND PITS	25	80	20

- CEMENT TYPE SHALL BE (ACSE SPECIFICATION) TYPE SL - PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 1379.

- 3. NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY AT & L.
- 4. CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE 40mm TOP AND 70mm FOR EXTERNAL EDGES UNLESS NOTED OTHERWISE.
- 5. ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- 6. THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS. COMPLETELY FILLING THE FORMWORK. THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED AND CURED IN ACCORDANCE WITH R.M.S SPECIFICATION R83.
- 7. REINFORCEMENT SYMBOLS:
- N DENOTES GRADE 450 N BARS TO AS 1302 GRADE N R DENOTES 230 R HOT ROLLED PLAIN BARS TO AS 1302
- SL DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS 1304 NUMBER OF BARS IN GROUP

8. FABRIC SHALL BE LAPPED IN ACCORDANCE WITH THE FOLLOWING

REFERANCE NUMBER FOR FABRIC TO AS 1304.

LAP TWO WIRES

KERBING NOTES

DETAIL

- 1. ALL CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 25MPa U.N.O IN REINFORCED CONCRETE NOTES.
- 2. ALL KERBS, GUTTERS, DISH DRAINS AND CROSSINGS TO BE CONSTRUCTED ON MIN. 100mm GRANULAR BASECOURSE COMPACTED TO MINIMUM 95% MODIFIED DRY DENSITY (AS 1289 5.2.1).
- 3. EXPANSION JOINTS (E.J) TO BE FORMED FROM 10mm COMPRESSIBLE CORK FILLER BOARD FOR THE FULL DEPTH OF THE SECTION AND CUT TO PROFILE. EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS. ON TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX 12m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE EXPANSION JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 4. WEAKENED PLANE JOINTS TO BE MIN 3mm WIDE AND LOCATED AT 3m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE WEAKENED PLANE JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 5. BROOMED FINISH TO ALL RAMPED AND VEHICULAR CROSSINGS, ALL OTHER KERBING OR DISH DRAINS TO BE STEEL FLOAT FINISHED.
- 6. IN THE REPLACEMENT OF KERB AND GUTTER :-EXISTING ROAD PAVEMENT IS TO BE SAWCUT 900mm U.N.O FROM THE LIP OF GUTTER. UPON COMPLETION OF THE NEW KERB AND GUTTER NEW BASECOURSE AND SURFACE TO BE LAID 900mm WIDE U.N.O.
- EXISTING ALLOTMENT DRAINAGE PIPES ARE TO BE BUILT INTO THE NEW KERB AND GUTTER WITH 100mm DIA HOLE.

EXISTING KERB AND GUTTER IS TO BE COMPLETELY REMOVED WHERE NEW KERB AND GUTTER IS SHOWN.

- 11. WATER AND FERTILIZE LANDSCAPE AS REQUIRED BY CLIMACTIC CONDITIONS TO ENSURE THE LANDSCAPE IS SUCCESSFUL.
- 12. AT THE COMPLETION OF WORK WRITTEN CONFIRMATION & CERTIFICATION IS TO BE PROVIDED FROM A QUALIFIED & EXPERIENCED GEOTECHNICAL ENGINEER THAT THE EMBANKMENTS HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THESE DRAWINGS.

Bar Scales ISSUED FOR DEVELOPMENT APPLICATION 19-04-21 22-12-20 ISSUED FOR DEVELOPMENT APPLICATION Date Description

100mm on Original

STORMWATER DRAINAGE NOTES

. STORMWATER DESIGN CRITERIA: (A) AVERAGE RECURRENCE INTERVAL:

- 1:100 YEARS MAJOR STORM (OVERLAND FLOW) 1:20 YEARS MINOR STORM (PIPED NETWORK)
- (B) RAINFALL INTENSITIES: TIME OF CONCENTRATION:5 MINUTES
- 1:100 YEARS= 219 mm/hr 1:20 YEARS= 167 mm/hi (C) RUNOFF COEFFICIENTS:

IN HEIGHT.

- ROOF AREAS: C 100 =1.0 EXTERNAL PAVEMENTS: C 100 =1.0
- . PIPES 300 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '3' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O. 3. PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC WITH SOLVENT WELDED JOINTS.
- . EQUIVALENT STRENGTH VCP OR FRC PIPES MAY BE USED, SUBJECT TO THE APPROVAL OF PENRITH CITY COUNCIL.
- ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE 6. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m
- . PIPES TO BE INSTALLED TO TYPE HS1 SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- . ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 (1998) AND AS/NZS 3500 3.2
- 8. PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY AT & L.
- . ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED
- FITTINGS WHERE PIPES ARE LESS THAN 300 DIA 0. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED. 1 CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL.
- 2. GRATES AND COVERS SHALL CONFORM TO AS 3996.
- 13. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 4. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS **REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER** FOR FURTHER DIRECTIONS.

EMBANKMENT CONSTRUCTION SEQUENCE

- 1. STRIP VEGETATION AND TOPSOIL FROM EMBANKMENT AREA AND STOCKPILE TOPSOIL FOR LATER USE. CUT BACK AREA TO FIRM GROUND.
- 2. CONSTRUCT EMBANKMENT IN PRESENCE OF QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER IF NOT ROCK.
- 3. IN THE CASE WHERE THE EMBANKMENT AREAS SLUSH, GROUTING AND DENTAL CONCRETE MAY BE REQUIRED, AS DIRECTED BY A QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER.
- 4. COMPACT CLAY STABILIZED WITH GYPSUM (3% BY DRY MASS, MINIMUM) AS APPROVED BY A QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER INTO THE CUT-OFF TRENCH OF LAYERS NOT EXCEEDING 150mm LOOSE THICKNESS TO A DRY DENSITY EQUIVALENT TO 98% OF THAT DETERMINED BY STANDARD COMPACTION (AS 1289.5.1.1) AND AT A MOISTURE CONTENT OF -2% TO +2% OF OPTIMUM MOISTURE CONTENT.
- 5. GYPSUM STABILIZED NATURAL SOILS EXPOSED IN EMBANKMENT AREA WITH MINIMUM 3% GYPSUM BY DRY MASS AND COMPACT AS FOR #4. ALL TO THE APPROVAL OF A QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER.
- 6. CONSTRUCT BODY OF EMBANKMENT WITH CLAYEY MATERIAL WON FROM SITE. COMPACT THE CLAYEY MATERIAL APPROVED BY A QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER IN LAYERS NOT EXCEEDING 150mm THICKNESS TO A DRY DENSITY EQUIVALENT TO 98% OF THAT DETERMINED BY STANDARD COMPACTION (AS 1289.5.1.1) AND AT A MOISTURE CONTENT OF -2% TO +2% OF OPTIMUM MOISTURE CONTENT. MOST IMPORTANTLY, IF SHRINKAGE CRACKS OCCUR, AS DIRECTED BY A QUALIFIED AND EXPERIENCED GEOTECHNICAL ENGINEER.
- 7. OVERFILL THE EMBANKMENT AND TRIM OFF, SO THAT THE ENTIRE BODY OF THE EMBANKMENT IS COMPACTED.
- 8. TRIM THE EMBANKMENTS BATTERS TO THE OVERFILLED MATERIAL, STABILIZE THE UPSTREAM CLAY BATTERS WITH WELL MIXED GYPSUM (3% BY DRY MASS, MINIMUM) AND COMPACT
- 9. PLACE ROCK RIP-RAP AS SHOWN.
- 10. RECOVER TOPSOIL FROM STOCKPILE AND SPREAD OVER EMBANKMENT AND CUT BATTERS (A THIN COVER OF TOPSOIL ONLY HAS BEEN NOMINATED). ONLY LIGHTLY TRACK-ROLL THE TOPSOIL AND THEN LANDSCAPE IN ACCORDANCE WITH THE LANDSCAPE AREA DRAWINGS.

Client

THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- 1. THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- 2. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS b. EPA REQUIREMENTS
- c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION". 4th EDITION. MARCH 2004.
- 3. MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.
- 4. WHEN STORMWATER PITS ARE CONSTRUCTED. PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.
- 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL. THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE: (A) INSTALL A WIND FENCE ALONG THE BOUNDARIES
- AS SHOWN ON PLAN. REFER DETAIL. (B) INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES
- AS SHOWN ON PLAN. REFER DETAIL.
- (C) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL.
- (D) INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- (E) INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN.
- (F) UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS. INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 10. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN **10 WORKING DAYS FROM PLACEMENT**
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE. I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY: (A) PROTECTING THEM WITH BARRIER FENCING OR SIMILAR
- MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- (B) ENSURING THAT NOTHING IS NAILED TO THEM (C) PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE
- FOLLOWING CONDITIONS. (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER
- TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

EROSION AND SEDIMENT CONTROL NOTES CONTINUED

STAGING

SUITABLE EROSION AND SEDIMENT CONTROLS SHALL BE DESIGNED, PROVIDED AND MAINTAINED BY THE CONTRACTOR THROUGHOUT ALL STAGES OF WORKS. INCLUDING AT COMPLETION OF THE BULK EARTHWORKS WHERE SHOWN ON AT&L DRAWINGS OR WHERE DIRECTED BY THE SUPERINTENDENT OR PENRITH CITY COUNCIL'S ENGINEERS.

SEDIMENT AND EROSION CONTROLS ARE TO BE DESIGNED AND DOCUMENTED BY A SUITABLY QUALIFIED EXPERT ENGAGED BY THE CONTRACTOR AND APPROVED AS PART OF THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SUCH CONTROLS SHALL BE IN ACCORDANCE WITH THE RELEVANT REQUIREMENTS IN THE LATEST VERSION OF THE MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION GUIDELINE (LANDCOM).

DEWATERING

ANY DEWATERING WORKS TO BE AS PER THE DEWATERING PROCEDURE AS CONTAINED WITHIN THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN (CEMP).

DECOMMISSIONING / DEMOLITION

DEMOLITION OF EXISTING DWELLING TO BE CONDUCTED IN ACCORDANCE WITH THE PROVISIONS OF AS2601-2001 - DEMOLITION OF STRUCTURES BY CONTRACTORS EXPERIENCED IN THIS CLASS OF WORK AND HOLDING REQUIRED CURRENT PERMITS AND LICENSES AS REQUIRED.

EXISTING INTERNALS FENCING, CATTLE YARDS, UTILITIES AND OTHER REDUNDANT STRUCTURES TO BE DEMOLISHED AND REMOVED TO AN APPROVED WASTE MANAGEMENT FACILITY.

DAM DECOMMISSIONING TO BE COMPLETED AS PER THE DAM DECOMMISSIONING PROCEDURE AS CONTAINED WITHIN THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN (CEMP).

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.

AT & L CAN NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY.

CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.

CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

PDK

Scales

BIO-RETENTION FILTER MEDIA SPECIFICATION MATERIALS:

BIO-RETENTION FILTER MEDIA, TRANSITION LAYER AND DRAINAGE LAYERS TO BE IN ACCORDANCE WITH CURRENT VERSION OF FAWB DOCUMENT "STORMWATER BIO-FILTRATION SYSTEMS ADOPTION GUIDELINES" AND THE FOLLOWING,

A) BIO-RETENTION FILTER MEDIA 1. BIO-RETENTION MEDIA IS TO BE FREE OF RUBBISH AND DELETERIOUS MATERIAL. 2. BIO-RETENTION FILTER MEDIA SATURATED HYDRAULIC CONDUCTIVITY TO BE 180mm/hr USING TEST METHOD ASTM F1815-06.

3. BIO-RETENTION FILTER MEDIA PARTICLE SIZE DISTRIBUTION IS TO BE AS FOLLOWS: CLAY & SILT <3% (<0.05mm)

VERY FINE SAND	5-30%	(0.05-0.15mm
FINE SAND	10-30% (0.1	5-0.25mm)
MEDIUM TO COARSE SAND	40-60%(0.2	5-1.0mm)
COARSE SAND	7-10%	(1.0-2.0mm)
FIN GRAVEL	<3%	(2.0-3.4mm)

THE COMBINED PERCENTAGE OF CLAY AND SILT MUST NOT EXCEED 3% (W/W) UNDER ANY CIRCUMSTANCES.

- 4. BIO-RETENTION FILTER MEDIA IS TO BE TESTED AND COMPLY WITH THE FOLLOWING REQUIREMENTS:
 - a) ORGANIC MATTER CONTENT IN ACCORDANCE WITH AS 4419 AT LEAST 3% (W/W) b) TOTAL NITROGEN (TN) CONTENT <900mg/kg c) ORTHOPHOSPHATE (PO43) CONTENT - <30mg/kg WHERE PLANTS WITH MODERATE PHOSPHOROUS SENSITIVITY ARE TO BE USED. TOTAL PHOSPHOROUS CONCENTRATION
 - SHOULD BE <20mg/kg
 - d) AS SPECIFIED FOR "NATURAL SOILS AND SOIL BLENDS" AS4419 pH 5.5-7.5 (pH 1.5 IN WATER)
 - e) ELECTRICAL CONDUCTIVITY (EC) AS SPECIFIED FOR "NATURAL SOILS AND SOILS BLENDS" AS4419 <1.2ds/m
 - f) DISPENSABILITY AS SPECIFIED FOR 'NATURAL SOILS AND SOIL BLENDS' AS4419 CATEGORY 1 OR 2 g) TEXTURE - LOAMY SAND AS PER AS4419
- 5. PRIOR TO PLACEMENT OF THE FILTER MEDIA A STATEMENT IS TO BE SUBMITTED FROM A QUALIFIED HORTICULTURIST CONFIRMING THAT THE SOIL IS CAPABLE OF SUPPORTING A HEALTHY VEGETABLE COMMUNITY.
- 6. TESTS CONFIRMING THE REQUIREMENTS OF ITEMS 1 TO 4 ARE TO BE SUBMITTED FOR APPROVAL PRIOR TO PLACEMENT OF FILTER MEDIA.

B) DRAINAGE LAYER A

DRAINAGE LAYER MATERIAL IS TO BE CLEAN, FINE GRAVEL, SUCH AS A 2 - 5mm WASHED SCREENING. THE PARTICLE SIZE DISTRIBUTION TO BE: D15 (DRAINAGE LAYER) < 5 x D85 (TRANSITION LAYER) WHERE: D15 (DRAINAGE LAYER) IS THE 15TH PERCENTILE PARTICLE SIZE IN THE TRANSITION LAYER MATERIAL (i.e, 15% OF THE SAND IS SMALLER THAN D15 mm), AND D85 (TRANSITION LAYER) IS THE 85th PERCENTILE PARTICLE SIZE IN THE FILTER MEDIA.


C) DRAINAGE LAYER B 10-20mm CLEAN GRAVEL WITH 2% VOLUME FINE STRAW AND 4-6% VOLUME HARDWOOD CHIPS.

INSTALLATION: FILTER MATERIAL IS TO BE LIGHTLY COMPACTED EG. A SINGLE PASS WITH A DRUM LAWN ROLLER. UNDER NO CIRCUMSTANCES SHOULD HEAVY EQUIPMENT OR MULTIPLE PASSES BE MADE. FILTER MEDIA SHOULD BE INSTALLED IN TWO LIFTS UNLESS THE DEPTH IS LESS THAN 500mm.

FINISHED SURFACE LEVELS


1. ALL FINISHED SURFACE LEVELS ARE ±2000mm U.N.O.





Project PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	
DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	atta Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
Title GENERAL NOTES	info@atl.net.au Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
	Project - Drawing No.	Issue
	20-748-C1002	В


F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1002.dwg



100mm on Original

	Client		Scales	1 . 9000	Drawn	PDK	Projec
THIS DRAWING CANNOT BE				1 : 2000	Designed	PDK	
COPIED OR REPRODUCED IN			Grid GDA	A94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN		ESR	Height Datum	AHD	Approved		
THAT ORIGINALLY INTENDED							Title
WITHOUT THE WRITTEN PERMISSION OF AT&L							

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1005.dwg




100mm on Original


F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1010.dwg

200mm – – UTILITY WARNING TAPES


600mm <u>TELECOMMUNICATIONS</u> MECHANICAL PROTECTION STRIP 750mm _ _ _ _ <u>ELECTRICAL CABLES</u> 900mm _ _ _ _ ELECTRICAL CABLES

1100mm----ADDITIONAL EXCAVATION





		Bar Scales		Client		Scales		Drawn	PDK	Project
			THIS DRAWING CANNOT BE			A	AS SHOWN	Designed	PDK	1
			COPIED OR REPRODUCED IN			Grid	GDA94 MGA56	Checked	TM	1
			ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	OTHER PURPOSE OTHER THAN	FCD	Height Datum	AHD	Approved		
		THAT ORIGINALLY INTENDE WITHOUT THE WRITTEN	THAT ORIGINALLY INTENDED	ESK	Durum			·	• Title	
B ISSUED FOR DEVELOPMENT APPLICATION	19-04-21									
A ISSUED FOR DEVELOPMENT APPLICATION	22-12-20		PERMISSION OF AT&L							
Issue Description	Date									
100mm on Original										




TYPICAL 4m VERGE TRENCH DETAIL SCALE 1:20

TYPICAL 5.0m VERGE TRENCH DETAIL

SCALE 1:20

ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
TYPICAL ROAD	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
SECTIONS SHEET 2	Project - Drawing No. 20-748-C1011	Issue B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1011.dwg



Scales	1.1500	Drawn	PDK	Proje
	1:1500	Designed	PDK	
Grid	GDA94 MGA56	Checked	ТМ	
Height Datum	AHD	Approved		Tul
				Title


LEGEND

- EXISTING BOUNDARY TO BE REMOVED
- ----- PROPOSED BOUNDARY
 - PROPOSED RETAINING WALL
 - INDICATIVE POND LAYOUT

ALL LEVELS SHOWN ± 2000mm U.N.O


^{oject} PROPOSED INDUSTRIAL DEVELOPMENT Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 ABBOTTS ROAD **KEMPS CREEK** www.atl.net.au info@atl.net.au Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION A1 Project - Drawing No. Issue 20-748-C1020 B


F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1020.dwg



^{ject} PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au				
BOUNDARY INTERFACE	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1			
SECTIONS SHEET 1	Project - Drawing No. 20-748-C1021	Issue B			


F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1021.dwg






	Client	Scales	Drawn	PDK	Project
THIS DRAWING CANNOT BE		AS SHOWN	Designed	PDK	1
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L		Height AHD Datum	Approved		• Title

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1023.dwg




Issue B


A1




FOR CONTINUATION REFER TO DRAWING CLOA2	LEGEND: EXISTING BOUNDARY EXISTING ELECTRICITY PROPOSED BOUNDARY PROPOSED BOUNDARY PROPOSED BOUNDARY PROPOSED FASEMENT NIDICATIVE POND LAYOUT PROPOSED RETAINING WALL PROPOSED MAJOR CONTOUR PROPOSED MINOR CONTOUR PROPOSED MAJOR CONTOUR PROPOSED BATTER CUT BATTER 1(V):3(h) FIL BATTER 1(V):5(H) U.N.O FUTURE SOUNDARY PROPOSED DRIVEWAY LAYBACK PROPOSED DRIVEWAY LAYBACK TO PCC SPECIFICATION FUTOR PROPOSED KERB RAMP LIMIT OF WORKS PROPOSED STORMWATER PROPOSED STORMWATER JUNCTION PIT PROPOSED STORMWATER SURFACE INLET PIT PROPOSED STORMWATER PROPOSED STORMWATER PROPOSED STORMWATER PROPOSED STORMWATER PROPOSED STORMWATER PIPE WITH HEADWALL PROPOSED STORMWATER LINE PROPOSED STORMWATER LINE PROPOSED STORMWATER LINE PROPOSED
INDICATIVE FUTURE ALDINGTON ROAD UPGRADE	ALL LEVELS ARE ±2000mm U.N.O KEYPLAN Image: State of the state
PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au
ROADWORKS AND STORMWATER DRAINAGE PLAN SHEET 1	Status PRELIMINARY A1 NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. Issue 20-748-C1041 B


rgs









F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1044.dwg








cales	1.050	Drawn	PDK	Proje
	1:250	Designed	PDK	
Frid	GDA94 MGA56	Checked	TM	
leight Datum	AHD	Approved		Title
				Title

	Г							
HORIZONTAL								
VC LENGTH						<	46.7n K=1	
GRADE	-	<		2.2%			->	<
Datum RL45								
PROPOSED SURFACE LEVEL	50.747	51.296	51.844	52.392	52.502	53.061	53.178	
EXISTING SURFACE LEVEL	50.747	51.246	51.823	52.387	52.502	52.984	53.057	
CHAINAGE	0.000	25.000	50.000	75.000	80.000	100.000	103.337	
	TP	:						

		Bar Scales		Client	Scales	1:100 V	Drawn	PDK	Proj
		0 2 4 6 8 10m 1 : 100 @ A1 1 : 200 @ A3 0 10 20 30 40 50m	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Grid Height Datum	1 : 500 H GDA94 MGA56 AHD	Designed Checked Approved	PDK TM	- Title
B ISSUED FOR DEVELOPMENT APPLICATION A ISSUED FOR DEVELOPMENT APPLICATION Issue Description	19-04-21 22-12-20 Date	1 : 500 @ A1 1 : 1000 @ A3	THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L						




MC01 LONGITUDINAL SECTION SCALE 1:500 HORL 1:100 VERT.

ABBOTTS ROAD (MC01) LONGITUDINAL SECTION SHEET 1 Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. Issue 20-748-C1050 B	PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	V 2060 05 777
	LONGITUDINAL SECTION	PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No.	Issue

		LP.= 65.681 M.O.= 0.188	0				
HORIZONTAL VC LENGTH			60m VC K=24				
GRADE	-	<u> </u>					7.5%
Datum RL54							
PROPOSED SURFACE LEVEL	I 65.460		67.084	67.931	68.930		
EXISTING SURFACE LEVEL	60.152	60.085	61.410	62.724	62.938		
CHAINAGE	350.000	356.674	375.000	386.674	400.000	425.000	450.000

	Bar Scales 0 2 4 6 8 10m 1 : 100 @ A1 1 : 200 @ A3 0 10 20 30 40 50m	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	Client ESR	Scales1 : 100 V 1 : 500 HGridGDA94 MGA56Height DatumAHD	Drawn Designed Checked Approved	PDK PDK TM	Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NS ABN 96 130 882 Tel: 02 9439 1 Fax: 02 9923 1 www.atl.net.au info@atl.net.au	SW 2060 2 405 1777
B ISSUED FOR DEVELOPMENT APPLICATION 19-04-2 A ISSUED FOR DEVELOPMENT APPLICATION 22-12-2 Issue Description Date	0 10 20 30 40 50m 1 : 500 @ A1 1 : 1000 @ A3	THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					ABBOTTS ROAD (MC01) LONGITUDINAL SECTION SHEET 2	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 20-748-C1051 al\SSDA\1000_INFRASTRUCTURE\20-748-C1051	Issue B




MC01 LONGITUDINAL SECTION SCALE 1:500 HORI. 1:100 VERT.

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1051.dwg

		0		0		
HORIZONTAL						
VC LENGTH						
GRADE				0.6	%	
Datum RL63	6		0	<u>م</u>	0	
PROPOSED SURFACE LEVEL	79.106	79.256	79.406	79.556	79.706	
EXISTING SURFACE LEVEL	80.721	78.185	73.735	68.921	68.663	
CHAINAGE	700.000	725.000	750.000	775.000	800.000	
				MC01 LONGITUDI SCALE 1:500 1:100 VER	HORI.	

			Bar Scales						
			-						
				0	2	4	6	8	10m
					1:	100 @ A1	1 : 200 @	• A3	
			-	0	10	20	30	40	50m
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21		-	1:5	600 @ A1	1:1000 @	₽ A3	
А	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20							
Issue	Description	Date							
	100mm on Original								



	Client	Scales 1:100 V	Drawn	PDK	Project .
THIS DRAWING CANNOT BE		1 : 500 H	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height AHD	Approved		
THAT ORIGINALLY INTENDED					Title
WITHOUT THE WRITTEN PERMISSION OF AT&L					
I LIUIDSION OF MIRE					1


PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	or Otroot
DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
ABBOTTS ROAD (MC01)	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
LONGITUDINAL SECTION SHEET 3	Project - Drawing No. 20-748-C1052	Issue B

 $\label{eq:F:20-748} ESR \ Mamre \ 6.0 \ Drgs \ Civil \ Final \ SSDA \ 1000 \ INFRASTRUCTURE \ 20-748-C1052. \ dwg$


	SAG	IP= 50.458 M.O.= 0.325					IP= 56.47 M.O.= -0.088		
HORIZONTAL VC LENGTH GRADE	-0.6%	50m VC K=9.6	>		4.6%		40m VC K=22.6	2.8%	>
Datum RL44 PROPOSED	50.608 50.599 50.591	50.783 50.821	51.692	2.842	53.992	5.142	56.234	57.037 57.068	57.344
SURFACE LEVEL 100 EXISTING 100	50.801 50 50.814 50 50.844 50	51.173 5(51.173 5(51.779 51.779 51.833 51.833 51.833	52.786 5:	5.	55.143 51 55.541 51 55.541 51	56.233 51 56.391 51	57.036 51 57.069 51	57.314 5
SURFACE LEVEL	23.186 25.000 28.956	48.186 50.000	73.186	100.000	125.000	150.000	175.000	198.878 200.000	209.732
đL			МС	CO2 LONGITUDINAL SCALE 1:500 HORL 1:100 VERT.	SECTION				
		Bar Scales				Client			Scales
			2 4 6 1:100@A1 1:200 10 20 30	8 10m) @ A3 40 50m	COPIED OR RE ANY FORM OR OTHER PURPOS	G CANNOT BE EPRODUCED IN USED FOR ANY SE OTHER THAN LLY INTENDED		SR	Grid G Height Datum

	Bar Scales 0 2 4 6 8 10m 1 : 100 @ A1 1 : 200 @ A3 0 10 20 30 40 50m	Clie THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ECD	Scales 1 : 100 V 1 : 500 H Grid GDA94 MGA56 Height AHD	Drawn Designed Checked Approved	PDK PDK TM	Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 W North Sydney I ABN 96 130 88 Tel: 02 9438 Fax: 02 9923 www.atl.net.au info@atl.net.au	882 405 39 1777 23 1055 Nu
BISSUED FOR DEVELOPMENT APPLICATION19-04-2AISSUED FOR DEVELOPMENT APPLICATION22-12-2IssueDescriptionDate	10 20 30 40 300 $1 : 500 @ A1 1 : 1000 @ A3$	THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	LJR				ALDINGTON ROAD (MC02) LONGITUDINAL SECTION SHEET 1	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTIO Project - Drawing No. 20-748-C1055	DN A1 Issue B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1055.dwg




├───┤		
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21
A	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20
Issue	Description	Date
	100mm on Original	I



	Client	Scales	Drawn	PDK	Proje
THIS DRAWING CANNOT BE		1 : 2000	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height Datum AHD	Approved		T '41
THAT ORIGINALLY INTENDED				<u>.</u>	Title
WITHOUT THE WRITTEN PERMISSION OF AT&L					

PROPOSED INDUSTRIAL	Civil Engineers and Project Managers			
DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	V 2060 05 77		
STORMWATER DRAINAGE	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1		
CATCHMENT PLAN (PRE-DEVELOPED)	Project - Drawing No. 20-748-C1061	Issue B		

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1061.dwg




1	:	2000	@	A

OR DEVELOPMENT APPLICATION	
OR DEVELOPMENT APPLICATION	
Description	

100mm on Original


	Client	1 . 0000		PDK	iiojeet
THIS DRAWING CANNOT BE		1 : 2000	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height AHD Datum AHD	Approved		
THAT ORIGINALLY INTENDED				1	Title
WITHOUT THE WRITTEN PERMISSION OF AT&L					
T ERMISSION OF ATAL					

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1065.dwg



	Client		Diawii	PDK	Project
THIS DRAWING CANNOT BE		1 : 250	Designed	PDK	
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid GDA94 MGA56	Checked	TM	
OTHER PURPOSE OTHER THAN	ES	Height AHD	Approved		Title
THAT ORIGINALLY INTENDED					litte
WITHOUT THE WRITTEN PERMISSION OF AT&L					

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1071.dwg




SECTION	$\overline{1}$
1:50	C1071


	Client	Scales		Drawn	PDK	Projec
THIS DRAWING CANNOT BE			1:50	Designed	PDK	
COPIED OR REPRODUCED IN		Grid	GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height Datum		Approved		
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L						• Title

PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
BIO-RETENTION BASIN SECTION	Info@atl.net.au Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No.	A1 Issue
	20-748-C1072	В

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1072.dwg



				508.330
				esti-
				LOT 3 DP250002
			Bar Scales	
B	ISSUED FOR DEVELOPMENT APPLICATION ISSUED FOR DEVELOPMENT APPLICATION	19-04-21 22-12-20		1 : 1000 @ A1 1 : 2000 @ A3
Issue		Date		



	Client	Scales	Drawn	PDK	Project
THIS DRAWING CANNOT BE		1 : 1000	Designed	PDK	
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid GDA94 MGA56	Checked	TM	
OTHER PURPOSE OTHER THAN		Height AHD Datum	Approved		Title
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					The

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1081.dwg

Datum RL26			
BOTTOM OF RETAINING WALL	58.526	58.296	57.558
TOP OF RETAINING WALL	59.055	59.026	59.123
HEIGHT OF RETAINING WALL	0.529	0.730	1.566
CHAINAGE	86.694	96.694	106.694

RETAINING WALL RW011B (THIRD TIER) PROFILE

SCALE 1:500 HORI. 1:500 VERT.


WALL AREA = 599m²

D. DIAA													
Datum RL23													
BOTTOM OF													
	6/	74	52	c	ç	02	45	03	94	25	13	01	24
RETAINING WALL	7.2	20.5	55.7	4.80	80.50 20.00 20.00	2.90	52.04	51.30	51.00	51.62	52.213	52.80	53.42
		2	ν <u>τ</u> ο τ	Ω 1	<u>n</u>	2	Ĵ.	37	2	5	7 C	27	5 5
TOP OF													
	22				326	606	992	.325	388	.285	369	226)83)97
RETAINING WALL	2.89	58.5	28.5	57.7	2.90	55.6	54.6	54.3	54.(54.2	54.3	54.2	54.08
HEIGHT OF													
	221	26	75	<u> </u>	41	44	47	61	94	60	56	25	50
RETAINING WALL	1.2	1.926	2.775	2.933	2.941	2.94	2.947	2.961	2.99	2.660	2.156	1.425	0.659
						0	0	0	0	0	0	0	5 0
CHAINAGE	00	000	000			00	00.0	.000	00.	000	00.0	00.0	240.000 252.102
	0.0	20.	40.	60.	80.	100	120	140	160	180	20(22(24(

<u> </u>			Bar Scales						
				0	2	4	6	8	10m
					1:10	00 @ A1	1 : 200 @	A3	
			-	0	10	20	30	40	50m
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21			1:50	0 @ A1	1:1000@	• A3	
Α	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20							
Issue	Description	Date							
-	100mm on Original	•	-						

		Client	Scales	Drawn	PDK	Project
	THIS DRAWING CANNOT BE		1 : 500	Designed	PDK	1
)m I	COPIED OR REPRODUCED IN		Grid GDA94 MGA5	6 Checked	TM]
	ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height AHD Datum AHD	Approved		
)m I	THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					- Title

RETAINING WALL RW011A PROFILE SCALE 1:500 HORL 1:500 VERT.



NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS

ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au					
RETAINING WALL	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1				
PROFILES SHEET 1	Project - Drawing No. 20-748-C1085	Issue B				

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1085.dwg

	REFER BELOW FOR CONTINUATION	WALL AREA = 523m ²									
	OR										_
	CON										
	INILI										
	UATI										
	NO										
D. DIAA											
Datum RL26											<u> </u>
BOTTOM OF RETAINING WALL	54.470	54 185 1		54.499	54.500	54.482	54.464	54.446	54.428	54.410	54.400
	54.	۲ ۲		54	54	54	54.	54	54	54.	54.
TOP OF	58.523	58 608		58.874	59.542	58.563	57.563	56.563	55.563	54.563	
RETAINING WALL	58.5	2		58.1	59.	58.5	57.	56.	55.	54.	
HEIGHT OF	~	-	1 4	4	~	-	6	~		с С	
RETAINING WALL	4.053	N 910		4.374	5.042	4.081	3.099	2.117	1.135	0.153	
CHAINAGE	0	S	2	0	0	0	8	8	8	00	85
UNAINAGE	300.000	390 000 290 000		340.000	360.000	380.000	400.000	420.000	440.000	460.000	470.785


	WALL AREA = 1006m ²	•											
Datum RL26 BOTTOM OF RETAINING WALL	58.493	57.582	56.669	267.66	04.0/1		4.04	4.77	C00.20				54.440
TOP OF RETAINING WALL	59.076	59.241	59.071	267.96	1/8.16	ç.)ç	0.149 9		58.662	58.3/3	58 .323	58 .333	
HEIGHT OF RETAINING WALL	0.583	1.659	2.403	000.0	000.0		9.402	4.175	3.957	3.738	3.758		3.918
CHAINAGE	0.000	20.000	40.000		0000	1000.000	000.071	140.000	160.000		Z001.000	220.000	-, -,

Image: state in the state		405 777 055 A1
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	--------------------------------

RETAINING WALL RW011B PROFILE SCALE 1:500 HORI. 1:500 VERT.

RETAINING WALL RW011B PROFILE SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



RE

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1086.dwg

WALL AREA = 600m²

	REFER BELOW							
Datum RL31 BOTTOM OF RETAINING WALL	59.236	59.057	59.216	59.037	59.196	59.017	59.227	59.050
TOP OF RETAINING WALL	66.048	65.817	65.586	64.306	63.045	61.784	60.523	59.3 59.127
HEIGHT OF RETAINING WALL	6.811	6.760	6.370	5.270	3.849	2.767	1.296	0.222 0.077
CHAINAGE	300.000	320.000	340.000	360.000	380.000	400.000	420.000	440.000 442.944

WALL AREA = 1656m²

									·····					
Datum RL31														
		ł	1	ł	1		ł	ł	ł	1	1	i	1	
BOTTOM OF														
	34	66	9/	31)4)1	[4	11	34	01	62	22	35	8/
RETAINING WALL	.664	6.0	.37	.18		2(.3]	.22	.33	.4(.42	.46	.48	.2.
	61.	26	59	29	59	26	59	599	20	59	599	20	59	26
TOP OF														
	74	46	36	82	228		38	461	34	46	154	38	56	81
RETAINING WALL	61.67	3.4	5.0	5.5	5.8	65.2	5.3	65.4	65.55	65.4	63.05	3.2	4.5	5.5
	9	ġ	9	65	9	9	9	9	9	9	6	ē	ė	9
HEIGHT OF														
	0	2	0	1	33	1	33	6	6	6	5		<u> </u>	3
RETAINING WALL	0.010	.44		.40	.56	6.06	80	6.239	.19	.05	3.62	3.78	5.07	30
	0	ŝ	5	9	0	6.	.9	9	0	6.	3	č,	2.	6
											0	0	0	0
CHAINAGE	0	00	00	00	00	000	000	000	000)) O	00	00	00	00
	000	0.0	0.0	0.0	0.0	00.0	50.0	10.0	90.0	80.0	00.	50.1	40.0	30.0
	0.	20	40	90	8	10	12	14	16	18	5(22	24	26


	Image: Solution of the second state	Bar Scales 0 2 4 6 8 10m 1 : 100 @ A1 1 : 200 @ A3 0 10 20 30 40 50m 1 : 500 @ A1 1 : 1000 @ A3	Clien THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	nt	Scales 1:500 Grid GDA94 MGA56 Height Datum AHD	Drawn Designed Checked Approved	PDK PDK TM	Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK Title RETAINING WALL PROFILES SHEET 3	Civil Engineers and Project Managers Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 20-748-C1087
--	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	------------------------------------------------------------	------------------------------------------	------------------	-----------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

RETAINING WALL RW012 PROFILE

SCALE 1:500 HORI. 1:500 VERT.

RETAINING WALL RW012 PROFILE SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1087.dwg

WALL AREA = 84m ²	REFER BELOW			
Datum RL38				
BOTTOM OF RETAINING WALL		66.040	- 620.060	66.130 -
TOP OF RETAINING WALL		70.12	68.107	67.06
HEIGHT OF RETAINING WALL		4.080	2.082	0.930
CHAINAGE		300.000	320.000	335.485

WALL AREA = 132m ²				
Datum RL35 BOTTOM OF RETAINING WALL	65.440	04.448	63.448	63.147 64.840
TOP OF RETAINING WALL				65.938 65.786
HEIGHT OF RETAINING WALL	-	/11-1	2.363	2.791 0.946
CHAINAGE	00000	000.02	40.000	60.000 76.925

RETAINING WALL RW022 PROFILE SCALE 1:500 HORI. 1:500 VERT.

WALL AREA = 1818m²


Datum RL37														
BOTTOM OF RETAINING WALL	65.496	65.979	65.996	65.822	65.929	65.920	65.949	65.940	65.969	65.960	65.989	65.935	66.035	65.971
TOP OF RETAINING WALL	65.496	67.034	69.032	70.912	72.796	73.113	73.17	73.285	73.4	73.508	73.572	73.636	73.7	72.798
HEIGHT OF RETAINING WALL	0.000	1.055	3.036	5.089	6.867	7.193	7.222	7.345	7.431	7.548	7.583	7.701	7.665	6.827
CHAINAGE	0.000	20.000	40.000	60.000	80.000	100.000	120.000	140.000	160.000	180.000	200.000	220.000	240.000	260.000

0 2 4 6 8 10m CO 1:100@A1 1:200@A3 0 10 20 30 40 50m TH	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		1 : 500 Grid GDA94 MGA	Designed 56 ^{Checked}	PDK TM	
	OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	ESR	Height AHD Datum	Approved		- Title

RETAINING WALL RW023 PROFILE SCALE 1:500 HORI. 1:500 VERT.

RETAINING WALL RW022 PROFILE SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
RETAINING WALL PROFILES SHEET 4	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 20-748-C1088	A1 ^{Issue} B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1088.dwg

VALL AREA = 18m ²		
Datum RL46		
BOTTOM OF RETAINING WALL	74.052	74.138 - 74.138 -
TOP OF RETAINING WALL	75.769	74.282 74.2
HEIGHT OF RETAINING WALL	1.716	0.144 0.062
CHAINAGE	300.000	320.000 321.137

RETAINING WALL RW024 PROFILE SCALE 1:500 HORI. 1:500 VERT.

	WALL AREA = 1	1483m²														
Datam DI 45																
Datum RL45	 															
BOTTOM OF		6	2	5	2	0	2	0	~	0	~	8	8	6	0	
RETAINING WALL	3.80	3.879	3.95	3.82	3.95	3.87(3.97	3.890	3.99	3.91(4.017	3.86	4.018	.3.90	4.01	
		2	2	2	2	2	2	2	6	6	6	2	2	4	2	
TOP OF		32	32	10	33	11	12	96	11	8	8	96		20	62	
RETAINING WALL		74.70	76.26	20.62	0.62	79.27	79.36	79.56	79.6(79.64	79.58	79.56	79.8(82.5(78.57	
		-	-	-	-	-			-			-	-			
HEIGHT OF		~	Ŧ	•		2		0		ē	0		0	~	6	
RETAINING WALL		0.88	2.30	5.269	5.07!	5.407	5.40	5.706	5.664	5.73	5.566	5.734	5.872	8.59	4.569	
CHAINAGE		00	0	0	0	000	000	000	00	00	000	000	000	000	000	
	000(50.00	10.00	00.00	30.0(0.00.0	20.0	40.0	60.0	80.0	00.00	20.0	340.0	60.0	80.(

0 2 4 6 8 10m CO 1:100@A1 1:200@A3 0 10 20 30 40 50m TH	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		1 : 500 Grid GDA94 MGA	Designed 56 ^{Checked}	PDK TM	
	OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	ESR	Height AHD Datum	Approved		- Title

WALL AREA = 110m ²					
Datum RL43					
BOTTOM OF RETAINING WALL	73.350	216.11	70.963	72.879	73.300
TOP OF RETAINING WALL		13.132	73.911	73.757	73.757
HEIGHT OF RETAINING WALL		F. 9 7	2.949	0.878	0.457
CHAINAGE	0.000	0000	40.000	60.000	67.008

RETAINING WALL RW025 PROFILE SCALE 1:500 HORI. 1:500 VERT.

RETAINING WALL RW024 PROFILE SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walke North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 105 177
RETAINING WALL	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
PROFILES	Project - Drawing No.	Issue
SHEET 5	20-748-C1089	В

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1089.dwg

WALL AREA = 544m ²	DEEED DEI OW EOD CONTINITATION					
Datum RL52						
BOTTOM OF RETAINING WALL	79.839 -	70 795		- 618.67		- 78/.6/
TOP OF RETAINING WALL	85.351			84.348		/12.68
HEIGHT OF RETAINING WALL	5.512	80		4.2C.4	4.576	5.435
CHAINAGE	300.000	290 000	0000	340.000	360.000	380.000

RETAINING WALL RW032 PROFILE

782

79.7

85.331 84.343

5.549 4.331

400. 406.

757

000

SCALE 1:500 HORI. 1:500 VERT.

WALL AREA = 1382m²


Datum RL52						
BOTTOM OF RETAINING WALL	79.940	/ 9.831 70.001	. 19.881	108.6/	79.859	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
TOP OF RETAINING WALL	79.748	81./23	6.040 	84.704 0000000000000000000000000000000000	84.939 84.939	
HEIGHT OF RETAINING WALL	-0.192	768.1 262.0	3.704	4.913	4.988 5.080	>
CHAINAGE	0.000	0000.02	40.000	0000	80.000 1 00.000	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,

	Image: Sector of the sector	Scales $ \begin{array}{ccccccccccccccccccccccccccccccccccc$	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Client	Scales 1:500 Grid GDA94 MGA56 Height AHD Datum	Drawn Designed Checked Approved	PDK F	PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK Title DETAINING WALL	Civil Engineers and Project Managers Civil Engineers and Project Managers Level 7, 153 Walker Str North Sydney NSW 200 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 20-748-C1090	treet 060 A1 ssue B
--	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------	------------------------------------------------------------	------------------------------------------	-------	----------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------

WALL AREA = 87m²

Determ DI 40				
Datum RL49				
BOTTOM OF				
	9		-	9 9
RETAINING WALL	76.976	///.439	106.77	78.446 78.686
	92		2	78
TOP OF	5	8	0	ŝ
RETAINING WALL	79.102	200 02 210.6/	030. 9	79.063 78.99
	62		R/	79
HEIGHT OF				
	26	2	54	17)4
RETAINING WALL	2.126	6/c.1	1.134	0.617 0.304
CHAINAGE		2	3	00 12
	0.000	0000.02	40.000	60.000 67.077
	0	Ň	4	9 0

RETAINING WALL RW031 PROFILE SCALE 1:500 HORI. 1:500 VERT.



RETAINING WALL RW032 PROFILE SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1090.dwg


WALL AREA = 708m ²										
Datum RL52										
BOTTOM OF RETAINING WALL	79.950	80.227	80.230	80.177	80.124	80.072	80.021	79.916	79.896	79.970
TOP OF RETAINING WALL	79.815	82.032	84.987	86.585	286.78	86.895	84.624	82.288	80.559	79.843
HEIGHT OF RETAINING WALL	-0.135	1.804	4.758	6.408	7.863	6.822	4.604	2.372	0.663	-0.127
CHAINAGE	0.000	20.000	40.000	60.000	80.000	100.000	120.000	140.000	160.000	173.488

WALL AREA = 236m ²	
Datum RL52	
BOTTOM OF RETAINING WALL	80.197
TOP OF RETAINING WALL	80.443
HEIGHT OF RETAINING WALL	0.246
CHAINAGE	0.000

		Bai	r Scales						
				0	2	4	6	8	10m
					1:1	00 @ A1	1 : 200 @	A3	
				0	10	20	30	40	50m
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21			1:5)0 @ A1	1:1000@	P A3	
А	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20							
Issue	Description	Date							

100mm on Original

RETAINING WALL RW043 PROFILE SCALE 1:500 HORI. 1:500 VERT.



RETAINING WALL RW042 PROFILE

SCALE 1:500 HORI. 1:500 VERT.

	Client	Scales	Drawn	PDK	Project
THIS DRAWING CANNOT BE		1 : 500	Designed	PDK	1
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	ТМ	1
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height Datum AHD	Approved		Title
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS

PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	
DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	atta Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
	Status PRELIMINARY	A1
RETAINING WALL	NOT TO BE USED FOR CONSTRUCTION	
PROFILES	Project - Drawing No.	Issue
SHEET 7	20-748-C1091	В

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1091.dwg

WALL AREA = 1561m ²	REFER BELOW		
Datum RL34			
BOTTOM		003	808
RETAININ	G WALL	62.003	602.809
TOP OF		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	N
RETAININ	G WALL	71.613	/4.012
HEIGHT O			_
RETAININ	G WALL	9.610	11.203
CHAINAG	E	300.000	220.000

WALL AR	EA = 1032m ²											
Datum RL33												
BOTTOM OF RETAINING WALL	66.761	66.415	66.143	66.225	+C1.00	66.213	66.295	66.256	66.204	66.282	66.357	66.305
TOP OF RETAINING WALL		68.55	69.015	69.114 60.964		69.71	69.934	69.487	69.039	69.187	69.315	69.44 69.564
HEIGHT OF RETAINING WALL	0.017	2.135	2.872	2.888	3.307	3.497	3.640	3.230	2.834	2.906	2.959	3.135 3.403
CHAINAGE	0.000	20.000	40.000	60.000	000.001	120.000	140.000	160.000	180.000	200.000	220.000	240.000 260.000


Image: space of the space	Designed Checked Approved	PDK PDK TM	Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK Title RETAINING WALL PROFILES SHEET 8	Civil Engineers and Project Managers Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au Status A1 NOT TO BE USED FOR CONSTRUCTION Issue Project - Drawing No. Issue 20-748-C1092 B
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------	------------------	-----------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	340.000	12.760	76.411	63.651	
<u>ج</u>		1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	00		
· 2 · C	000.000	10, 01	(0.01 70 000	004.60 00	
	000.000	16.491	/9.90 0000000000000000000000000000000000	- 00.490	
N	400,000	10.745	C07.00	03.402	
		1.00 <del>11</del>	C11.00	CO 2177	
			00.770		
	460.256	-0.000 -0.000	80.437	80.437 -	

## **RETAINING WALL RW051 PROFILE** SCALE 1:500 HORI. 1:500 VERT.

#### **RETAINING WALL RW051 PROFILE** SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1092.dwg

#### WALL AREA = 1190m²

	REFER BELOW										
Datum RL41											
BOTTOM OF RETAINING WALL	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500
TOP OF RETAINING WALL	77.851	77.731	77.611	77.491	77.371	77.109	76.142	74.218	72.308	70.808	70.124
HEIGHT OF RETAINING WALL	8.351	8.231	8.111	7.991	7.871	7.609	6.642	4.718	2.808	1.308	0.624
CHAINAGE	300.000	320.000	340.000	360.000	380.000	400.000	420.000	440.000	460.000	480.000	489.120


WALL AREA = 233	33m²													
Datum RL41														
BOTTOM OF RETAINING WALL	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	69.500	
TOP OF RETAINING WALL	69.601	71.38	73.779	76.178	78.577	79.219	79.014	78.811	78.691	78.571	78.451	78.331	78.211	
HEIGHT OF RETAINING WALL	0.101	1.880	4.279	6.678	9.077	9.719	9.514	9.311	9.191	9.071	8.951	8.831	8.711	
CHAINAGE	0.000	20.000	40.000	60.000	80.000	100.000	120.000	140.000	160.000	180.000	200.000	220.000	240.000	

				Client	Scales	Drawn	PDK	Project PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	
	_		THIS DRAWING CANNOT BE		1 : 500	Designed	PDK	DEVELOPMENT	Level 7, 153 Wall North Sydney NS	
	_	0 2 4 6 8 10m	COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	ABBOTTS ROAD	ABN 96 130 882 Tel: 02 9439 1 Fax: 02 9923 1	1777
	_	1 : 100 @ A1 1 : 200 @ A3	ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	FSR	Height AHD Datum AHD	Approved		KEMPS CREEK	www.atl.net.au info@atl.net.au	
		0 10 20 30 40 50m	THAT ORIGINALLY INTENDED	EJK				litte	Status PRELIMINARY	
ISSUED FOR DEVELOPMENT APPLICATION 19-04-2	21	1:500 @ A1 1:1000 @ A3	WITHOUT THE WRITTEN					RETAINING WALL	<b>PRELIMINAR I</b> NOT TO BE USED FOR CONSTRUCTION	J A1
ISSUED FOR DEVELOPMENT APPLICATION 22-12-2	20		PERMISSION OF AT&L					PROFILES	Project - Drawing No.	Issue
Description Date	e							SHEET 9	20-748-C1093	B

#### **RETAINING WALL RW052 PROFILE** SCALE 1:500 HORL 1:500 VERT.

#### **RETAINING WALL RW052 PROFILE** SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1093.dwg

WALL AREA = 83m ²				
Datum RL39 BOTTOM OF RETAINING WALL	68.638	67.334	00	69.600
TOP OF RETAINING WALL	69.929	69.874	692 C 09	69.9
HEIGHT OF RETAINING WALL	1.291	2.540	5000	0.300
CHAINAGE	0.000	20.000		40.000

## **RETAINING WALL RW053 PROFILE** SCALE 1:500 HORI. 1:500 VERT.


#### WALL AREA = 1025m²

Datum RL33															
BOTTOM OF RETAINING WALL	61.333	60.762	61.359	62.889	62.770	62.723	62.805	62.723	62.727	62.628	62.575	62.545	69 790	007.70	63.416
TOP OF RETAINING WALL	69.995	66.181	66.367	66.291	66.235	66.288	66.305	66.223	66.186	66.238	66.235	66.153	961 99	001.000	66.274
HEIGHT OF RETAINING WALL	8.663	5.419	5.008	3.402	3.464	3.566	3.500	3.499	3.460	3.610	3.660	3.608	006 6	0000	2.858
CHAINAGE	0.000	20.000	40.000	00000	80.000	100.000	120.000	140.000	160.000	180.000	200.000	220.000		0000.047	260.000

Image: selection of the se	Scales 1 : 500 Grid GDA94 MGA56 Height Datum AHD	Drawn Designed Checked Approved	PDK PDK TM	Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers          Civil Engineers and Project Managers         Level 7, 153 Walker Street         North Sydney NSW 2060         ABN 96 130 882 405         Tel:       02 9439 1777         Fax:       02 9923 1055         www.atl.net.au         info@atl.net.au         Status       PRELIMINARY         NOT TO BE USED FOR CONSTRUCTION         Project - Drawing No.         20-748-C1094       B
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------	------------------------------------------	------------------	---------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

#### **RETAINING WALL RW054 PROFILE** SCALE 1:500 HORI. 1:500 VERT.

NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS



 $\label{eq:F:allow} F: \ ESR Mamre \ 6.0 Drgs \ Civil \ Final \ SSDA \ 1000 \ INFRASTRUCTURE \ 20-748-C1094. dwg$ 

WALL AREA = 55m ²				
Datum RL34				
BOTTOM OF				
<b>RETAINING WALL</b>	62.530	02.040	016.20	62.448 62.550
	62	50 50	20	62 62
TOP OF		c	ø	9
<b>RETAINING WALL</b>	61.85	C 9.70	03.030	63.516 62.56
			-	
HEIGHT OF	02	0	Ŷ	8 0
RETAINING WALL	-0.680	CUC.U	L.348	1.068
CHAINAGE	9	8	00	18 00
	0.000	ZUUUU	40.000	60.000 74.418

#### **RETAINING WALL RW062 PROFILE** SCALE 1:500 HORI. 1:500 VERT.

WALL AREA = 938m ²												
							┶╌┿╋╍┿╍┿╍┿╍┿╍┿╍┿╍┿╍┿╍┿╍┿╍	╘╬╉╏╍╬╍╬╍╬╍╬╍╬╍╬╍╬╍╬╸				
Datum DI 90												
Datum RL29												
BOTTOM OF	27	427	27	427	427	81	581	81	81	43	47	.386
RETAINING WALL	62.4	61.4	60.4	59.4	58.4	56.581	56.5	56.58	56.581	58.143	60.047	61.386 62.093
TOP OF												
RETAINING WALL		62.615	62.621	62.935	2.994	62.993	63.012	63.023	63.052	63.121	63.166	62.912 63.11
	;9	69	39		62.	<i>;</i> 9	60	69	<u></u>	39	39	<u> </u>
HEIGHT OF	2				~					~	-	
<b>RETAINING WALL</b>	-0.12	1.188	2.194	3.508	4.567	6.413	6.432	6.442	6.472	4.978	3.119	1.526
						_	_	_	_	_	2	
CHAINAGE	000	20.000	0.000	000.	000.	100.000	120.000	10.00	60.000	0000	00.00	220.000 231.053
	0.0	20	4(	60.	80.	10	12	14	16	180	2(	22 23

			Bar Scales						
				0	2	4	6	8	10m
					 1:1	.00 @ A1	1 : 200 @	, A3	
				0	10	20	30	40	50m
В	ISSUED FOR DEVELOPMENT APPLICATION	19-04-21			1:5	00 @ A1	1:1000@	₽ A3	
А	ISSUED FOR DEVELOPMENT APPLICATION	22-12-20							
Issue	Description	Date							

100mm on Original

	Client	Scales	Drawn	PDK	]
THIS DRAWING CANNOT BE		1 : 500	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	ТМ	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height AHD Datum AHD	Approved		┓
THAT ORIGINALLY INTENDED WITHOUT THE WRIITEN PERMISSION OF AT&L			-		


**RETAINING WALL RW061 PROFILE** SCALE 1:500 HORI. 1:500 VERT.


## **RETAINING WALL RW063 PROFILE**


SCALE 1:500 HORL 1:500 VERT.

WALL AREA = 191m ²				······································	J_1_
Datum RL32					
ΡΟΤΤΟΜ ΟΕ		1	1	1	I
BOTTOM OF	2	2	9	0	0
RETAINING WALL	62.467	61.587	60.746	60.440	60.700
	9	9	9	9	9
TOP OF					
<b>RETAINING WALL</b>	63.08	62.943	63.001	63.096	63.082
	63	62	63	63	63
HEIGHT OF					
	с.	9	22	9	5
RETAINING WALL	0.613	1.356	2.255	2.656	2.382
	-				
CHARMACE			_	_	_
CHAINAGE	0.000	20.000	40.000	60.000	80.000
	0.0	20.	40	60.	80.


NOTES: ALL FINISHED LEVELS ARE ±2000mm U.N.O REFER TO DRG C1020 FOR TYPICAL WALL SECTIONS







F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1095.dwg



# SERVICES LEGEND


EXISTING SERVICES

WATER MAIN ELECTRICITY OVERHEAD

#### PROPOSED SERVICES

ELECTRICITY TELECOMMUNICATION CONDUITS WATER MAIN SEWER SERVICE STORMWATER LINE UPSTREAM STORMWATER CATCHMENT DIVERSION LINE


LIGHT POLE




— — w — — w — — w —


	Civil Engineers and Project Managers	
PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
SERVICES AND UTILITIES	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
COORDINATION PLAN SHEET 1	Project - Drawing No. <b>20-748-C1101</b>	Issue B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1101.dwg





	<image/>	LOT 5 FEL70.00	POR CONTINUATION REFER TO	
Image: Second state     Image: Second state       Imag	0 10 20 30 40 50m 1 : 500 @ A1 1 : 1000 @ A3	COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	<b>ESR</b>	Grid       GDA94 MGA56       Checked       TM         Height Datum       AHD       Approved       Title




F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1103.dwg


20-748-C1103

B

SHEET 3




	ALL LEVELS SHOWN ± 2000mm U.N					٥.٧
DUSTRIAL MENT ROAD				Leve North	agers el 7, 153 Walker Stro h Sydney NSW 206 96 130 882 405 02 9439 1777	




DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au					
EROSION AND SEDIMENT	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1				
CONTROL DETAILS	Project - Drawing No.	Issue				
	20-748-C1210	В				
F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1210.dwg						

Civil Engineers and Project Managers




100mm on Original


F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1311.dwg




F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\1000_INFRASTRUCTURE\20-748-C1312.dwg



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2111.dwg




ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walke North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 105 177
LOT 01 PAVEMENT	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
PLAN	Project - Drawing No. 20-748-C2121	Issue <b>B</b>




	Client	Scales	Drawn	PDK	Pro
THIS DRAWING CANNOT BE		1:500	Designed	PDK	1
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid GDA94 MGA56	Checked	TM	
OTHER PURPOSE OTHER THAN		Height AHD Datum	Approved		Titl
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					S

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2211.dwg



		Client	Scales	Diawii	PDK	Projec
	THIS DRAWING CANNOT BE		1:500	Designed	PDK	1
	COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	]
n	ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height Datum AHD	Approved		
	THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					<b>T</b> itle

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2221.dwg




Proje Title S


	EXISTING BOUNDARY
	PROPOSED BOUNDARY
	PROPOSED EASEMENT
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	PROPOSED RETAINING WALL
	INDICATIVE POND LAYOUT
• F59.30	PROPOSED SPOT HEIGHT
2.0%	PROPOSED SURFACE GRADE
	PROPOSED BATTER FILL BATTER 1(V):5(H) CUT BATTER 1(V):3(H) U.N.O
K&G	PROPOSED KERB AND GUTTER
КО	PROPOSED DRIVEWAY KERB ONLY
$\frown$	PROPOSED KERB RAMP
	PROPOSED SAFETY BARRIER
< < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < < <	PROPOSED CATCH DRAIN
	PROPOSED STORMWATER JUNCTION PIT
	PROPOSED STORMWATER SURFACE INLET PIT
-	PROPOSED STORMWATER KERB INLET PIT WITH LINTEL
	PROPOSED STORMWATER PIPE WITH HEADWALL
Ø600	PROPOSED STORMWATER LINE WITI SIZE AND DIRECTION
	PROPOSED UPSTREAM STORMWATE DIVERSION LINE
	PROPOSED 300mm WIDE GRATED DRAIN WITH CLASS D GRATE

LOT 03 ITEWORKS AND STORMWATER DRAINAGE PLAN Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. Issue	ect PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walke North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 05 77
	<b>ITEWORKS AND STORMWATER</b>	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	

· ___ · ___ · ___ · ___

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2311.dwg






ALL LEVELS SHOWN ARE ±2000mm U.N.O

-85 n

Civil Engineers and Project Managers PROPOSED INDUSTRIAL Level 7, 153 Walker Street North Sydney NSW 2060 DEVELOPMENT ABN 96 130 882 405 **ABBOTTS ROAD** Tel: 02 9439 1777 **KEMPS CREEK** Fax: 02 9923 1055 www.atl.net.au info@atl.net.au LOT 03 Status PRELIMINARY A1 SITEWORKS AND STORMWATER NOT TO BE USED FOR CONSTRUCTION DRAINAGE PLAN Project - Drawing No. Issue 20-748-C2312 SHEET 2 B

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2312.dwg




	• • • • • • • • • •	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·			· · · · · · · · · · · · · · · · · · ·	
			< < < < <				
			LOT S FFL80.				
				Scales	Drawn		<u> </u>
			Client	Scales 1:500		PDK	Pr
		VING CANNOT BE			Designed	PDK	
m		REPRODUCED IN OR USED FOR ANY		Grid GDA94 M	GA56 Checked	TM	
		A REAL PROPERTY AND A REAL PROPERTY AND A		-			

	Client		Scales 1 500	Drawn	PDK	Project
THIS DRAWING CANNOT BE			1:500	Designed	PDK	
COPIED OR REPRODUCED IN			Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN		FSR	Height Datum AHD	Approved		(T): - 1
THAT ORIGINALLY INTENDED						Title
WITHOUT THE WRITTEN PERMISSION OF AT&L						

LEGE	END
	<u>HEAVY DUTY HARDSTAND</u> TO BE CONFIRMED AT DETAILED DESIGN
	LIGHT DUTY CAR PARK TO BE CONFIRMED AT DETAILED DESIGN
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	<u>LANDSCAPING</u> REFER TO LANDSCAPE ARCHITECTS DRAWINGS FOR DETAILS
	<u>FOOTPATH PAVEMENT</u> TO BE CONFIRMED AT DETAILED DESIGN
	<u>STRUCTURAL</u> REFER TO STRUCTURAL DRAWINGS FOR DETAILS
	FIRE ACCESS TRACK TO BE CONFIRMED

PROPOSED INDUSTRIAL	Civil Engineers and Project Managers	
DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
LOT 03 PAVEMENT	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1
PLAN SHEET 1	Project - Drawing No. 20-748-C2321	Issue <b>B</b>
		D

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2321.dwg



LOT 3 FFL80.00				
Client	Scales 1:500	Drawn	PDK	Proj
THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN	Grid GDA94 MGA56	Designed Checked	PDK TM	
		1	1 11/1	

ESR

Height Datum

AHD

Approved

ANY FORM OR USED FOR ANY

OTHER PURPOSE OTHER THAN


THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN

PERMISSION OF AT&L

LEGE	ND
	<u>HEAVY DUTY HARDSTAND</u> TO BE CONFIRMED AT DETAILED DESIGN
	LIGHT DUTY CAR PARK TO BE CONFIRMED AT DETAILED DESIGN
	<u>LANDSCAPING</u> REFER TO LANDSCAPE ARCHITECTS DRAWINGS FOR DETAILS
	<u>FOOTPATH PAVEMENT</u> TO BE CONFIRMED AT DETAILED DESIGN
	STRUCTURAL REFER TO STRUCTURAL DRAWINGS FOR DETAILS
	FIRE ACCESS TRACK TO BE CONFIRMED
POND LAY	OUT OPTION
	SWALE
	MAINTENANCE TRACK
	<u>RIP RAP SPILLWAY</u>


Project PROPOSED INDUSTRIAL DEVELOPMENT ABBOTTS ROAD KEMPS CREEK	Civil Engineers and Project Managers Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au	N 2060 105 777
Title LOT 03, LOT 04 & LOT 5 PAVEMENT PLAN	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION Project - Drawing No.	A1 Issue
SHEET 2	20-748-C2322	В

 $F:\20-748\ ESR\ Mamre\6.0\ Drgs\Civil\Final\SSDA\2000_ON\ LOT\20-748-C2322.dwg$ 




	Client		Scales	1.700	Diawii	PDK	Project
THIS DRAWING CANNOT BE				1:500	Designed	PDK	
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY			Grid <b>G</b>	DA94 MGA56	Checked	TM	
OTHER PURPOSE OTHER THAN		ESR	Height Datum	AHD	Approved		
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN							Title SITI
PERMISSION OF AT&L							

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2411.dwg



100mm on Original

	Client		Scales		Diawii	PDK	Proje
THIS DRAWING CANNOT BE				1:500	Designed	PDK	
COPIED OR REPRODUCED IN			Grid	GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN		ESR	Heigh Datum		Approved		Title
THAT ORIGINALLY INTENDED							litte
WITHOUT THE WRITTEN PERMISSION OF AT&L							SI
I ERMISSION OF ATAL							




· — · —

ALL LEVELS SHOWN ARE ±2000mm U.N.O

Project PROPOSED INDUSTRIAL Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 DEVELOPMENT ABN 96 130 882 405 **ABBOTTS ROAD** Tel: 02 9439 1777 Fax: 02 9923 1055 **KEMPS CREEK** www.atl.net.au info@atl.net.au LOT 04 Status PRELIMINARY A1 **SITEWORKS AND STORMWATER** NOT TO BE USED FOR CONSTRUCTION DRAINAGE PLAN Project - Drawing No. Issue SHEET 2 20-748-C2412 В

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2412.dwg




Scales	1 500	Drawn	PDK	Project	
	1:500	Designed	PDK		
Grid	GDA94 MGA56	Checked	TM		
Height Datum	AHD	Approved		Title	
				litte	

LEGEND					
	<u>HEAVY DUTY HARDSTAND</u> TO BE CONFIRMED AT DETAILED DESIGN				
	LIGHT DUTY CAR PARK TO BE CONFIRMED AT DETAILED DESIGN				
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	LANDSCAPING REFER TO LANDSCAPE ARCHITECTS DRAWINGS FOR DETAILS				
	FOOTPATH PAVEMENT TO BE CONFIRMED AT DETAILED DESIGN				
	<u>STRUCTURAL</u> REFER TO STRUCTURAL DRAWINGS FOR DETAILS				
	FIRE ACCESS TRACK TO BE CONFIRMED				
POND LAY	OUT OPTION				
	SWALE				
	MAINTENANCE TRACK				
	<u>RIP RAP SPILLWAY</u>				

PROPOSED INDUSTRIAL	Civil Engineers and Project Managers				
DEVELOPMENT ABBOTTS ROAD	Level 7, 153 Walk North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10	NSW 2060 82 405 9 1777			
KEMPS CREEK	Fax. 02 9923 for www.atl.net.au info@atl.net.au	55			
LOT 04 & LOT 5 PAVEMENT	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	A1			
PLAN SHEET 1	Project - Drawing No. 20-748-C2421	Issue B			

F:20-748 ESR Mamre6.0 Drgs $CivilFinalSSDA2000_ON LOT20-748-C2421.dwg$ 





_____

			Б				
	Client	Scales	Drawn	PDK	Project DDODOCED MIDUCTDIAL	Civil Engineers and Project Managers	
		1:500			PROPOSED INDUSTRIAL		<b>O</b>
THE DRAWING CANNOT DE		1.000	Designed	PDK	DEVELOPMENT	Level 7, 153 Walke North Sydney NSV	er Street
THIS DRAWING CANNOT BE				I DR		ABN 96 130 882 4	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	ABBOTTS ROAD	Tel: 02 9439 17	
ANY FORM OR USED FOR ANY		and abriot marioo		1111	KEMPS CREEK	Fax: 02 9923 10	
		Height AHD	Approved		<b>NEIVIPS UNEEN</b>	www.atl.net.au	
OTHER PURPOSE OTHER THAN		Datum AIID			Title	info@atl.net.au	
THAT ORIGINALLY INTENDED					LOT 04 & LOT 5	Status	
WITHOUT THE WRITTEN						PRELIMINARY	A1
					PAVEMENT	NOT TO BE USED FOR CONSTRUCTION	
PERMISSION OF AT&L					PLAN		
					<b>FLAN</b>	Project - Drawing No.	Issue
					SHEET 2	20-748-C2422	B

LEGEND					
	HEAVY DUTY HARDSTAND TO BE CONFIRMED AT DETAILED DESIGN				
	LIGHT DUTY CAR PARK TO BE CONFIRMED AT DETAILED DESIGN				
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	LANDSCAPING REFER TO LANDSCAPE ARCHITECTS DRAWINGS FOR DETAILS				
	<u>FOOTPATH PAVEMENT</u> TO BE CONFIRMED AT DETAILED DESIGN				
	<u>STRUCTURAL</u> REFER TO STRUCTURAL DRAWINGS FOR DETAILS				
	FIRE ACCESS TRACK TO BE CONFIRMED				
POND LAY	OUT OPTION				
	SWALE				
	MAINTENANCE TRACK				
	<u>RIP RAP SPILLWAY</u>				

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2422.dwg






100mm on Original


	Client		Diawii	PDK	Proje
THIS DRAWING CANNOT BE		1 : 500	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	ESR	Height AHD	Approved		T: 1
THAT ORIGINALLY INTENDED			7		Title
WITHOUT THE WRITTEN PERMISSION OF AT&L					

F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2512.dwg




	Cheffe	1.500		IDK	5
THIS DRAWING CANNOT BE		1:500	Designed	PDK	
COPIED OR REPRODUCED IN		Grid GDA94 MGA56	Checked	TM	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	<b>FSR</b>	Height AHD	Approved		
THAT ORIGINALLY INTENDED					Title
WITHOUT THE WRITTEN					
PERMISSION OF AT&L					


			OT 5 POND TWL 70.00 UME 52,246m ³ CE AREA 29,018m ²	BBOTTS ROAD
B     ISSUED FOR DEVELOPMENT APPLICATION     19-04-21       A     ISSUED FOR DEVELOPMENT APPLICATION     22-12-20       Issue     Description     Date	Bar Scales 0 10 20 30 40 50m 1 : 500 @ A1 1 : 1000 @ A3	Client THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Grid GDA94	DrawnPDKProjectionDesignedPDKPDKMGA56CheckedTMHDApprovedTitle



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2522.dwg



			,		- 1	1
		_			FI	<b>F</b> 3
		<u>ki</u>				
				Bar Scales		
					0 10 20	30 40 50m
					1 : 500 @ A1	1 : 1000 @ A3
В	ISSUED FOR DEVELOPMENT APPLICAT	ION	19-04-21			
A	ISSUED FOR INFORMATION		22-12-20			
Issue	Descriptio	n	Date			
	1	100mm on Orig				



F:\20-748 ESR Mamre\6.0 Drgs\Civil\Final\SSDA\2000_ON LOT\20-748-C2621.dwg